

AD-A069 594

NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/6 13/2
NATIONAL DAM SAFETY PROGRAM. CRYSTAL SPRING LAKE (NJ 00231), PA--ETC(U)
MAY 79 R J JENNY

DACW61-78-C-0124

UNCLASSIFIED

NL

1 OF 2

AD
A069594



LEVEL

PASSAIC RIVER BASIN
RAMSEY BROOK
BERGEN COUNTY
NEW JERSEY

C
P-5.

A069594

**CRYSTAL SPRING
LAKE
NJ 00231**

DDC
RECEIVED
JUN 8 1979

**PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



Approved for public release;
distribution unlimited

DDC FILE COPY

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

May, 1979

79 06 01 076

NOTICE

**THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00231	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Crystal Spring Lake Bergen County, New Jersey	5. TYPE OF REPORT & PERIOD COVERED 9 FINAL rept.	
7. AUTHOR(s) 10 Robert J. Jenny P.E.	6. PERFORMING ORG. REPORT NUMBER	
	8. CONTRACT OR GRANT NUMBER(s) 15 DACW61-78-C-0124	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Jenny-Leedshill Engineering 318 South Orange Ave. South Orange, N.J. 07079	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106	12. REPORT DATE 11 May 79	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 6 National Dam Safety Program, Crystal Spring Lake (NJ 00231), Passaic River Basin, Ramsey Brook, Bergen County, New Jersey. Phase I Inspection Report.	13. NUMBER OF PAGES 98	
	15. SECURITY CLASS. (of this report) Unclassified	
15a. DECLASSIFICATION/DOWNGRADING SCHEDULE		
16. DISTRIBUTION STATEMENT Approved for public release; distribution unlimited. 12 116p.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams Riprap Spillways National Dam Inspection Act Report Embankments Crystal Spring Dam, N.J. Overtopping		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		



IN REPLY REFER TO

NAPEN-D

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, NJ 08621

18 MAY 1979

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Crystal Spring Lake Dam in Bergen County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Crystal Spring Lake Dam, a high hazard potential structure, is judged to be in fair to poor overall condition. The dam's spillway is considered inadequate since 11 percent of the Probable Maximum Flood (PMF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

- a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system, should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.
- b. Within six months from the date of approval of this report, engineering studies and analyses should be initiated to determine the dam's embankment condition and structural stability. This should include test borings to determine material properties relative to stability and seepage. Any remedial measures found necessary should be initiated within calendar year 1980.
- c. The source of seepage near the left side of the embankment should

29 06 01 076

NAPEN-D

Honorable Brendan T. Byrne

be determined within three months from the date of approval of this report. If the seepage is determined to be from the reservoir, the seriousness of it should be evaluated and remedial measures implemented.

d. Within six months from the date of approval of this report, the following remedial actions should be completed:

(1) Riprap should be placed on the upstream slope and rock facing on the downstream slope of the embankments to provide at least minimal protection in times of overtopping.

(2) Remove all trees and brush from the embankment.

(3) Repair any excessively steep slopes of the embankment to a stable slope.

(4) Repair and clean out the outlet area of the emergency drain and regularly operate the valves to verify that they are in working order.

e. Inspect the dam yearly, and immediately after any overtopping. Make timely repairs as necessary and keep records of all maintenance work.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Andrew Maguire of the Seventh District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.


Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/ _____	
Availability Codes	
Dist	Available for special
A	

NAPEN-D

Honorable Brendan T. Byrne

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



JAMES G. TON
Colonel, Corps of Engineers
District Engineer

1 Incl
As stated

Copies furnished:

Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

John O'Dowd, Acting Chief
Bureau of Flood Plain Management
Division of Water Resources
N. J. Dept. of Environmental Protection
P. O. Box CN029
Trenton, NJ 08625

CRYSTAL SPRING LAKE DAM (NJ00231)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 30 November 1978 and 4 January 1979 by Jenny-Leedshill Engineers under contract to the State of New Jersey. The State, under agreement with the U. S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Crystal Spring Lake Dam, a high hazard potential structure, is judged to be in fair to poor overall condition. The dam's spillway is considered inadequate since 11 percent of the Probable Maximum Flood (PMF) would overtop the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system, should be promptly developed. Also, during periods of unusually heavy precipitation, around-the-clock surveillance should be provided.

b. Within six months from the date of approval of this report, engineering studies and analyses should be initiated to determine the dam's embankment condition and structural stability. This should include test borings to determine material properties relative to stability and seepage. Any remedial measures found necessary should be initiated within calendar year 1980.

c. The source of seepage near the left side of the embankment should be determined within three months from the date of approval of this report. If the seepage is determined to be from the reservoir, the seriousness of it should be evaluated and remedial measures implemented.

d. Within six months from the date of approval of this report, the following remedial actions should be completed:

(1) Riprap should be placed on the upstream slope and rock facing on the downstream slope of the embankments to provide at least minimal protection in times of overtopping.

- (2) Remove all trees and brush from the embankment.
- (3) Repair any excessively steep slopes of the embankment to a stable slope.
- (4) Repair and clean out the outlet area of the emergency drain and regularly operate the valves to verify that they are in working order.
- e. Inspect the dam yearly, and immediately after any overtopping. Make timely repairs as necessary and keep records of all maintenance work.

APPROVED: _____

James G. Ton
JAMES G. TON
Colonel, Corps of Engineers
District Engineer

DATE: _____

18 May 79

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Crystal Spring Lake,
I. D. No. NJ00231
State Located: New Jersey
County Located: Bergen
Stream: Ramsey Brook
Dates of Inspection: November 30, 1978 and January
4, 1979

Brief Assessment of General Condition of dam

The dam is generally in fair to poor overall condition. The spillway can pass 10 percent of the Probable Maximum Flood and is classified as inadequate. The spillway was recently repaired and appears to be in good condition.


Seepage of undetermined origin was observed near the toe of the embankment. The downstream embankment is very uneven, and both slopes are covered with a heavy growth of vegetation.

It is recommended that the source of seepage in the embankment be determined very soon and remedial measures implemented if it appears to endanger the dam. Seepage and stability analyses are recommended in the near future. More detailed and sophisticated hydraulic and hydrologic studies are recommended to more accurately determine the spillway capacity prior to any remedial action. Riprap and rock facing should be


placed on the embankment slopes.

Recommendations for operation and maintenance that should be implemented in the near future include:

(1) removal of vegetation from the embankments, (2) repair of locally steep slopes, (3) repair of the outlet drain and regular operation of the drain, (4) annual and post-flood inspection of the dam, (5) recording of all maintenance work, and (6) implementation of a warning system with specific notice to houses downstream of the dam as to flood potential and danger to life and property.



Frank L. Panuzio, P.E.
Project Manager



Robert J. Jenny, P.E.
Project Director
New Jersey License No. 9878



CRYSTAL SPRING DAM

Upstream view looking east. Spillway in center of photograph. (Nov. 30, 1978)

TABLE OF CONTENTS

	Page
BRIEF ASSESSMENT OF GENERAL CONDITION OF DAM	i
OVERVIEW PHOTOGRAPH	
PREFACE	
SECTION 1 PROJECT INFORMATION	
1.1 General	1
1.2 Description of Project	1
1.3 Pertinent Data	4
SECTION 2 ENGINEERING DATA	
2.1 Design	6
2.2 Construction	7
2.3 Operation	7
2.4 Evaluation	7
SECTION 3 VISUAL INSPECTION	
3.1 Findings	9
SECTION 4 OPERATIONAL PROCEDURES	
4.1 Procedures	13
4.2 Maintenance of Dam	13
4.3 Maintenance of Operating Facilities	13
4.4 Description of Warning Systems	14
4.5 Evaluation of Operational Adequacy	14
SECTION 5 HYDRAULIC/HYDROLOGIC	
5.1 Evaluation of Features	15

TABLE OF CONTENTS

(Continued)

	Page
SECTION 6 STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	21
SECTION 7 ASSESSMENT, RECOMMENDATIONS AND PROPOSED REMEDIAL MEASURES	
7.1 Dam Assessment	23
7.2 Remedial Measures	24

PLATES

1. Vicinity Map
2. Crystal Spring Lake Dam
 General View
3. Plan of Crystal Spring Lake Spillway

APPENDICES

APPENDIX A - Check List - Visual Observations
 Check List - Engineering, Construc-
 tion Maintenance Data

APPENDIX B - Photographs

1. Downstream embankment
2. Seepage near left abutment
3. Crest and upstream embankment
4. Downstream view of spillway
5. Flow over spillway weir
6. Reservoir drain outlet
7. Reservoir area

(Continued)

- APPENDIX C - Regional Geology - Piedmont Lowlands
- APPENDIX D - Hydrologic and Hydraulic Computations

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D. C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

CRYSTAL SPRING LAKE DAM

Federal I.D. No. NJ 00231

New Jersey I.D. No. 23-77

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The National Dam Inspection Act, Public Law 92-367, 1972, provides for the National Inventory and Inspection Program by the U. S. Army Corps of Engineers. This report has been prepared in accordance with this authority, through contract between the State of New Jersey and Jenny-Leedshill Engineers. The State of New Jersey has also entered into an agreement with the U.S. Army Engineer District, Philadelphia, to have this work performed.

b. Purpose of Inspection

The purpose of this inspection was to evaluate the general structural integrity and hydraulic adequacy of the dam, and to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project

a. Description of Dam and Appurtenances

Crystal Spring Lake Dam is an earthfill dam with a concrete core. The dam impounds a reservoir of 130

acre feet maximum storage capacity. The dam is approximately 550 feet long, 12 feet high, and has a crest width of 25 to 30 feet. A paved roadway traverses the entire length of the crest. Embankment slopes are highly variable on both the upstream and downstream sides, averaging about 2.5H:1V on the upstream side and 2H:1V on the downstream side. Locally, the downstream embankment is as steep as about 1.5H:1V. The spillway is a rubble masonry weir located near the right abutment. The 30-foot long weir is divided into 2 bays separated by a pier. The end walls and center pier support a bridge over the spillway. Downstream of the spillway a lined channel and masonry training walls direct flow through a 90 degree angle over a toe wall to the stream channel. The emergency outlet consists of 2 parallel 10-inch diameter pipes near the center of the dam, with controls located in a manhole in the crest of the dam.

b. Location

The dam is located across Ramsey Brook in northeastern New Jersey in the Borough of Ramsey, Bergen County, about 10 miles north of Paterson. The location of the dam is shown on Plate 1.

c. Size Classification

The size classification of the dam based on the 12-foot height of the dam and the maximum storage capacity of 130 acre feet is small. The criteria for size classification are set forth in the Corps' Guidelines. A small size dam is one in which the storage capacity is equal to or greater than 50 acre feet and less than 1000 acre feet, and/or the height of the dam is equal to or greater than 25 feet and less than 40 feet.

d. Hazard Classification

Crystal Spring Lake Dam is classified as a high hazard dam because of the potential damage and loss of more than a few lives that could occur in the event of dam failure at two residences immediately downstream and perhaps about 20 houses in community of Allendale (pop. 6,200) further downstream.

e. Ownership

The dam is owned by the Ramsey Golf and Country Club, Inc., 105 Lakeside Drive, Ramsey, New Jersey, 07446.

f. Purpose of Dam

The primary purpose of the dam and reservoir is for recreation and scenic value. A small amount of water is pumped from the reservoir for irrigation of the nearby golf course.

g. Design and Construction History

Crystal Spring Lake Dam, variously called Crystal Springs Dam, Crystal Lake Dam and Wyckoff Lake Dam, was built sometime prior to 1913. Correspondence in the owner's files indicates that the dam may have been built about the turn of the century. Wooden flashboards were added to the spillway in about 1966 but were removed shortly thereafter. In December, 1975 the State ordered the reservoir dewatered because the spillway could not pass the 100-year flood and because of deterioration of the existing spillway and possible underflow beneath it. The action was withheld in February, 1976 pending engineering studies. Repairs of the spillway were made in 1977 to the satisfaction of the State.

h. Normal Operational Procedures

The reservoir is unregulated, with flood flows passing over the ungated spillway weir. The emergency

outlet is only occasionally operated for maintenance work on the dam or to clean the reservoir.

1.3 Pertinent Data

- a. Drainage Area - 1.77 square miles
- b. Discharge at Damsite
 - . Ungated spillway capacity at maximum pool elevation - 450 cfs.
- c. Elevation (ft. above MSL)
 - . Top Dam 352.9
 - . Spillway crest 349.3
 - . Streambed at centerline of dam 341 (Approx.)
- d. Reservoir Length (ft.)
 - . Top of dam 2800
 - . Spillway Crest (recreation pool) 2100
- e. Storage (acre-feet)
 - . Spillway crest 65
 - . Top of dam 130
- f. Reservoir Surface (acres)
 - . Top dam 20
 - . Spillway crest 14
- g. Dam
 - . Type Earthfill with concrete core wall
 - . Length 550 ft. (approx.)
 - . Height 12 ft.
 - . Top Width 25 - 30 ft. (Paved road)
 - . Side Slopes - upstream 2.5H:1V (Estimated)
 - downstream 2H:1V (highly variable)

- . Zoning Not known
 - . Impervious Core Concrete core wall
- h. Spillway
- . Type Two-bay rubble masonry, free overfall
 - . Length of weir 30 ft.
 - . Width 2.5 ft.
 - . Crest elevation 349.3 ft.
 - . U/S Channel Reservoir
 - . D/S Channel Lined channel with masonry training walls
- i. Regulating Outlets
- . 2 parallel 10-in. diameter C.I. pipes and gate valves (emergency outlet)

SECTION 2: ENGINEERING DATA

2.1 Design

a. Geological Conditions

Crystal Spring Lake and Dam are situated in the northern New Jersey Piedmont Lowlands. The regional geology at this area is presented in Appendix C to this report.

Geologically, the dam is located in the broad, rolling ground moraine (till) plain deposited by the most recent continental glaciation. The ground moraine is characterized as a non-residual, unsorted and heterogeneous mixture of unstratified soil. The size of the materials range from clay through boulders with silt and sand sizes predominating. Permeability through this material is typically low to medium, depending on the amount of fines.

Within stream valleys, recent alluvium, typically derived from local materials, occupies the flood plains. Swampy ground with a high water table is usually found on either side of the immediate stream where it has not been altered by urbanization.

Bedrock was not observed at or near the dam and is probably located at depths greater than 20 feet below the present ground surface. At depth, the underlying formation is the Brunswick formation, a soft red shale with interbedded sandstone layers.

The dam is located in a Seismic Zone 1 and no active faults are known to exist in the immediate vicinity of the dam. However, seismic shaking due to distant earthquakes should be expected.

0

2.1 b. Design Data

No data are available pertaining to the original design of the dam. Based on field measurements at the time of inspection, the dam is believed to be substantially as shown in plan on Plate 2. The spillway and a downstream channel are shown in plan and elevation on Plate 3.

2.2 Construction

Nothing is known of the original construction methods nor of as-built embankment materials. It was reported that the concrete core wall was constructed 18 inches thick and about 14 feet deep. In 1977 the spillway weir and downstream apron were repaired as shown on Plate 3.

2.3 Operation

No records of reservoir levels are maintained by the owner. Records of recent repairs are available. There are no monitoring devices or survey markers on the dam.

2.4 Evaluation

a. Availability

Data are not available on the original design or construction of the dam or on as-built material properties. Data are available on recent repairs of the spillway. All available data are listed in Appendix A.

b. Adequacy

Available data are insufficient to adequately evaluate the design. Calculations relating to the structural design of the dam or the stability of the

as-built structure are not available. Nothing is known of construction methods, testing methods, or as-built material properties. Foundation conditions are unknown.

c. Validity

Because no recent surveys of the dam have been made other than at the spillway, the crest elevation of the dam is not known with precision. Plans of the spillway (Plate 3) appear to adequately represent the present configuration. The information on the core wall was reported in the owner's correspondence and by a local caretaker, and there is no assurance of its validity.

SECTION 3: VISUAL INSPECTION

3.1 Findings

a. General

The visual inspection of Crystal Spring Lake Dam was made on November 30, 1978 and a subsequent inspection made on January 4, 1979. The water surface elevation at the time of the first inspection was 349.5 feet or just above the top of the spillway crest.

The visual inspection did not reveal any critical signs of distress in the dam; however, generally the dam has not been well maintained.

Although certain remedial work has been done at the spillway in recent years, it was apparent from the visual inspection that there has been little or no maintenance work on the embankment in many years.

Detailed inspection was made of the dam, appurtenant structures, reservoir area, and the downstream channel. Descriptions of the findings of these inspections are summarized in the paragraphs which follow. The checklist of visual inspection items is included in Appendix A. Geologic and foundation conditions observed at the time of inspection are noted in greater detail in Section 2.1-a.

b. Dam

The dam was inspected for signs of settlement, seepage, erosion, cracking and any other evidence of undesirable behavior which might affect the stability of the structure.

An asphalt paved roadway transverses the entire length of the top of the dam, including a bridge deck over the spillway. There is no evidence of settlement or horizontal misalignment of the crest. Both the upstream and downstream slopes of the embankment are very uneven. The unevenness of the downstream slope is probably attributable to a number of factors, including erosion from overtopping and rainfall runoff, the action of large tree roots, and the buildup of debris over the years. There is a heavy growth of trees, up to 2 feet in diameter, on the downstream slope (Photo 1). Scattered large boulders on this slope may be remnants of a rock facing. The junctions of the embankment with its abutment and with the spillway appear to be tight, with no evidence of separation or movement.

About 2 to 5 gpm seepage was noted flowing from a 15-foot wide area at the toe of the embankment, approximately 100 feet from the left (east) abutment. (Photo 2). The discharge was clear but there was some indication of possible quick conditions. The source of the seepage could be from the reservoir, from recent precipitation runoff, or it could be related to a sewer line which is reported to have pierced the embankment and concrete core in this vicinity. The area below the toe is marshy.

Little of the upstream embankment was exposed above the waterline. There is no evidence that the embankment has a riprap facing. The embankment is covered with a heavy growth of vegetation (Photo 3).

c. Appurtenant Structures

Spillway

The spillway is a 2-bay overflow weir separated by a bridge deck support pier (Photo 4). Because of its rock masonry construction, discharge over the weir was rather uneven, but the crest and downstream face appeared to be in good condition, with no evidence of erosion or plucking of the masonry (Photo 5). The center bridge pier and masonry training walls have been repaired recently and are in good condition. A new toe wall has been installed at the base of the spillway apron (Photo 4), and the underside of the bridge was recently covered with wire mesh and gunite.

Outlet Works

Little of the emergency drain could be observed. It is reported to consist of 2 10-inch pipes controlled by valves in a manhole on the crest of the dam. The manhole was observed to be filled with water to the level of the reservoir and the valves were submerged in 9 feet of water. The downstream outlet was obscured by debris. There was about 1/2 gpm seepage from the outlet area (Photo 6).

d. Reservoir Area

Water in the reservoir was clear and without any evidence of sediment. It was reported, however, that there is a sedimentation problem requiring dredging

of the lake bottom.

Slopes around the reservoir are gentle and wooded (Photo 7). Numerous houses face the reservoir on the surrounding roadways.

e. Downstream Channel

A concrete lined channel with vertical block and masonry training walls extends about 70 feet downstream from the toe of the spillway apron, terminating at a low weir (Photo 8). A house is located on the right bank of the lined channel (Photo 9) and there is another house in the flood plain downstream. Below the lined channel, the natural stream meanders considerably and the flow channel is not well defined in places. The overbank flood channel has moderate slopes and is heavily wooded.

SECTION 4: OPERATIONAL PROCEDURES

4.1 Procedures

The reservoir is operated to maintain maximum water levels for recreational and aesthetic purposes. A minor amount of water is pumped from the reservoir to irrigate an adjacent golf course. There is no regulation of reservoir levels other than for occasional inspections and maintenance work. Sediment has been dredged from the reservoir on at least one occasion.

4.2 Maintenance of Dam

There has apparently been little or no maintenance work done on the embankment in many years.

The spillway weir and downstream apron were repaired in 1977. This work included patching of concrete in the masonry walls, removal of concrete stop blocks (for flashboards) on the upstream side of the spillway, repairs of the apron, construction of a new toe wall at the end of the apron, and installation of wire mesh and gunite on the bottom surface of the bridge over the spillway.

There are no instrumentation or monitoring systems on the dam or reservoir.

4.3 Maintenance of Operating Facilities

The emergency outlet is apparently operated only

occasionally. The manhole housing the valve controls is flooded, but the valves reportedly can be operated without draining the manhole. It is not known what maintenance work has been done on the outlet.

4.4 Description of Warning System

There is no warning system or emergency contingency plan in event of possible dam failure or overtopping.

4.5 Evaluation of Operational Adequacy

In general, maintenance of the dam has been deficient. Recent work to repair the spillway and appurtenances was of good quality. Other than this recent work, there are no records of operations or maintenance.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design Data

As already stated, Crystal Spring Lake Dam is classified as high hazard and small in size. In accordance with the Corps of Engineers' "Recommended Guidelines for Safety Inspection of Dams", the Spillway Design Flood (SDF) should be 50 to 100 percent of the Probable Maximum Flood (PMF). The 100 percent PMF was selected as the SDF because of the high hazard to loss of life immediately downstream of the dam.

Data obtained from State files indicate the drainage basin area of the dam is 1.77 square miles. Elevations range from a maximum of about 640 feet above mean sea level along the perimeter of the drainage basin to a minimum of about 350 feet in the valley floor. Land use patterns within the watershed consist mostly of forests and cultivated land. Only a minor portion of the basin is residential developments. About 1 percent of the watershed area is the reservoir of the dam. The drainage basin is delineated on a U.S.G.S. topographic map and is presented on Plate D-1, Appendix D.

The hydraulic and hydrologic features of the dam were evaluated using criteria set forth in the Corps of Engineers' "Recommended Guidelines for Safety Inspection of Dams", and additional guidance and criteria provided by the Philadelphia District, Corps of Engineers. The Probable Maximum Precipitation (PMP) was calculated using Hydrometeorological Report No. 33 and the standard Hops Brook reduction factor of 0.80 for misalignment of the storm.

The Probable Maximum Flood (PMF) was calculated using the Corps' computer program HEC-1, Dam Break Version. In computing the PMF the Corps requested that the SCS triangular unit hydrograph with curvilinear transformation be used. The computer program was used to calculate this unit hydrograph from the basin lag. A lag time of 1.1 hours was calculated for the basin and used in the program.

An initial infiltration loss of 1.5 inches and a final infiltration loss rate of 0.15 inches per hour were used in the HEC-1 program to give the rainfall excess. Using the excess rainfall and the unit hydrograph, the program computed the peak inflow of the 10 percent, 15 percent, 50 percent and 100 percent PMF. These discharges are approximately 610 cfs, 920 cfs, 3070 cfs, and 6140 cfs, respectively.

The various percentages of the PMF inflow hydrograph were routed through the reservoir using the Modified Puls Method by the HEC-1 program. The peak outflow discharges of the 10 percent, 15 percent, 50 percent, and 100 percent PMF were calculated to be approximately 420 cfs, 840 cfs, 3060 cfs and 6130 cfs, respectively. The flood routings indicate that all floods greater than about 10 percent of the PMF will overtop the dam. A plot of percent PMF versus peak outflow is presented as Plate D-2 in Appendix D.

The spillway and overtop stage-discharge rating curve used in the flood routing was calculated using the weir equation and the orifice equation. For all flows up to the bottom elevation of the bridge over the spillway the weir equation was used assuming free overflow. The spillway is a broad-crested weir with a discharge coefficient of 2.9. For flows above the bottom elevation of the

bridge, the orifice equation was used to calculate flows through the spillway, and a discharge coefficient of 0.61 was assumed. To calculate flows over the dam crest, the weir equation was used and free overflow as assumed. The dam crest is a round-crested weir with trees and other vegetation. A discharge coefficient of 2.6 was assumed. The reservoir stage-storage curve was determined from U.S.G.S. 7.5-minute topographic maps and data obtained from State files. This stage-storage curve was extended above the dam crest to include surcharge storage during peak flood discharges. In the reservoir routing computations possible discharges through the outlet works were excluded because their capacity is small compared to the PMF and because of the possibility that the outlet valves may be closed. The stage-storage and the spillway and overtop stage-discharge curves are presented in Appendix D as Plates D-3 and D-4, respectively.

Because the spillway cannot pass one-half the PMF, the various percentages of the PMF, assuming the dam would not breach and assuming the dam would breach, were routed 1.2 miles downstream through three successive reaches to the community of Allendale. For the routing calculations, estimates of channel shapes, slopes and roughnesses were made based on conditions observed in the field and U.S.G.S. topographic maps. The locations of the cross-sections used in these routings are shown on page D-9, Appendix D.

The breach parameters used in the HEC-1 analysis are: the breach is rectangular in shape, 270 feet long, will extend to the approximate original reservoir floor elevation (340'), will begin breaching when the dam is first overtopped, and will develop to its maximum size in 4.0 hours. The peak outflow for the 10 percent, 15 percent,

50 percent and 100 percent PMF were calculated to be approximately 420 cfs, 1480 cfs, 3560 cfs, and 6410 cfs, respectively.

Three floods were compared in assessing the downstream hazard: (1) the PMF assuming the dam is breached; (2) the PMF assuming the dam is not breached; and (3) the flood that is approximately equal to the existing capacity of the spillway (10% PMF). The flood depth, width and mean flow velocity of these three floods at the community of Allendale are summarized in the following tabulation.

Flooding Characteristics at Allendale			
	10% PMF Without <u>Breaching</u>	PMF Without <u>Breaching</u>	PMF With <u>Breaching</u>
Peak Discharge, cfs	420	5900	6260
Peak Flood Depth, ft.	1.8	4.6	4.7
Peak Flood Top			
Width, ft.	50	700	710
Peak Flow Velocity, fps	4.7	4.9	4.9

There are two parallel drain pipes for the reservoir. A representative of the dam owner indicated that one drain pipe is 8 inches in diameter and the other is 12 inches in diameter. Drawings obtained from the owner's engineer indicate the drain pipes are both 10 inches in diameter. The two 10-inch diameter pipes have less capacity and were assumed in this analysis. Using the orifice flow equation, and assuming no inflow into the reservoir or outlet tailwater, the time required to drain the reservoir from a spillway crest elevation was calculated to be a little over 4 days.

b. Experience Data

Records of lake levels are not maintained for this site. The reservoir is operated to maintain maximum water levels for aesthetic and recreational purposes. It is reported that the dam was overtopped as recently as July, 1977, but the flooding characteristics of this flood are not known.

c. Visual Observations

Just downstream of the spillway there is a masonry training wall and spillway channel that turns flow through a 90-degree angle and directs it along the downstream toe of the dam towards the main channel. This wall and channel diverts most flows away from the two homes located just downstream of the spillway. A resident of one of the downstream homes reported that during the flood of July, 1977 her house was almost inundated and her neighbor's house was inundated. Thus, the training wall and spillway channel are not adequate to divert all of the larger floods that overtop the dam away from the hazard area.

The main stream channel downstream of the dam has a very irregular cross section, low channel banks and many meanders. The immediate flood plain slopes gently into the main stream, is thickly wooded and has considerable undergrowth.

d. Overtopping Potential

As indicated in Section 5.1-a, all floods greater than about 10 percent of the PMF, when routed through the reservoir, will overtop Crystal Spring Lake Dam. The PMF will overtop the dam by 2.4 feet for 7.3 hours. One-half the PMF will overtop the dam 1.4 feet for 5.8 hours. These overtopping heights assume the dam remains in its current condition. Thus, a dam breach analysis, described

in Section 5.1-a, was made because the spillway may be Seriously Inadequate. One of the Corps' criteria for classifying a spillway as Seriously Inadequate is, "Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream from the dam from that which would exist just before overtopping failure."

The data tabulated in Section 5.1-a were used to assess the degree of significance that overtopping failure would increase the downstream hazard. Assuming the dam does not breach, the discharge at Allendale would be about 5900 cfs as compared to a breach peak discharge of about 6260 cfs. The flow depth, top width and velocity would be only slightly greater during the breach peak discharge and not result in a significantly higher downstream hazard. Thus, the spillway is classified as Inadequate.

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

The embankment slopes, particularly those downstream, are very uneven. There is a heavy growth of vegetation on the slopes, including numerous large trees. Seepage at the rate of 2 to 5 gpm was observed from one area of the embankment on the left side of the dam. The source of the seepage could not be determined. The crest of the embankment has no visually obvious vertical or horizontal misalignments.

The spillway appears to be structurally sound, as is the lined channel downstream. The condition of the reservoir drain could not be determined.

b. Design and Construction Data

Almost nothing is known of the design or construction of the dam. Nothing is known of as-built embankment materials, and no original hydrologic or hydraulic computations are known to exist. Engineering drawings prepared for rehabilitation of the spillway are adequate and represent as-built conditions.

c. Operating Records

No records of reservoir levels are maintained

by the owner, nor is there any systemitized recording of maintenance events. There have been no recent surveys of the embankments of the dam. There is no instrumentation of the dam.

d. Post-Construction Changes

The only known post-construction change is the rehabilitation of the spillway and appurtenant structures. It appears that this work was well engineered and well constructed. Because of the age of this dam, it is likely that there have been other post-construction changes, about which nothing is known.

e. Seismic Stability

The dam is located in Seismic Zone 1, in which it may generally be assumed that there is no hazard from earthquake, provided static stability conditions are satisfactory and conventional safety margins exist. Although the dam appears to have satisfactory static stability, a stability analysis would be required to verify this.

SECTION 7: ASSESSMENT, RECOMMENDATIONS
AND PROPOSED REMEDIAL MEASURES

7.1 Dam Assessment

a. Safety

The spillway can pass only 10 percent of the Probable Maximum Flood. The dam has been overtopped a number of times, most recently in 1977. At least one house is known to have been inundated in the most recent flood. There are a few residences immediately downstream which are endangered by overtopping and the community of Allendale is further downstream.

The embankment is very uneven, shows signs of erosion, and is heavily overgrown by vegetation. Seepage of undeterminable origin was observed near the toe of the dam.

The spillway appears to be in good structural condition. The outlet works are seldom operated and their condition is unknown.

b. Adequacy of Information

There are insufficient data to evaluate the stability of the dam, since nothing is known of the design, construction methods, or as-built properties of the dam. Recent data indicate the presence of a concrete core wall, and although there is no reason to doubt this information, its presence was not

verified by the visual inspection. There have been no recent surveys of the embankment, and there are conflicting data regarding the size of the two outlet drains.

c. Urgency

The source of apparent embankment seepage should be determined very soon. Consideration should be given in the future to construction of a supplemental spillway. Other recommendations should be implemented in the near future.

d. Necessity for Additional Data/Evaluation

Corps of Engineers Guidelines require that, in general, seepage and stability analysis should be on record for all high hazard dams. In view of the hazard potential of this dam and the possible seepage problem, it is recommended that such analyses be performed by the owner, including soil borings and laboratory tests of embankment and foundation materials.

7.2 Remedial Measures

a. Corrective Procedures

The following corrective procedures are recommended:

(1) The source of seepage near the left side of the embankment should be determined very soon. If the seepage is determined to be from the reservoir, the seriousness of it should be evaluated and immediate remedial measures implemented.

(2) The owner should undertake more detailed and sophisticated hydraulic and hydrologic studies to more accurately determine the spillway capacity. Depending on the results of these studies, remedial action should be taken as required.

(3) In the near future riprap should be placed on the upstream slope and rock facing on the downstream slope of the embankments to provide at least minimal protection in times of overtopping.

b. Operation and Maintenance Procedures

The following operation and maintenance procedures are recommended to be implemented in the near future:

(1) Remove all trees and brush from the embankment, since the roots endanger the core wall and could lead to piping problems.

(2) Repair any excessively steep slopes of the embankment to a stable slope.

(3) Repair and clean out the outlet area of the emergency drain and regularly operate the valves to verify that they are in working order.

(4) Inspect the dam yearly, and immediately after any overtopping, and make timely repairs as necessary.

(5) Keep records of all maintenance work.

(6) Implement a warning system in cooperation with local authorities and devise a contingency plan in event of flooding conditions or possible failure of the dam. Post warning signs or give specific notice to houses downstream of the dam as to flood potential and danger to life and property.



1000 0 1000 2000 3000 4000 5000 6000
 SCALE IN FEET




AREA LOCATION

VICINITY MAP

JENNY - LEEDSHILL

JANUARY 1979



Scale 1"=100'

CRYSTAL SPRING DAM GENERAL VIEW

Hand-drawn plan view of a bridge section showing two spans, labeled "A" and "B".

- Span "A" length: 12.11
- Pier width (between spans): 18.02
- Span "B" length: 12.11
- Pier width (between spans): 18.02
- Abutment width (left): 18.02
- Abutment width (right): 18.02
- Centerline elevation: EL 342.5
- Pier elevation: EL 349.27
- Abutment elevation: EL 349



DRIVE

VALVE MH

RAV'T EL. 332

6" GL. WA:

6" C.I. WATER LINE.

33.0

TOP WALL
FL 34293

E13400

563400

Edge of spillway

BB000447 CONC

PROPOSED GROUTED RIP RAP -

DD WAL
AT 90

EXIST. TWO 10" CIP

AE 337.80
TOP WALL
31.340.47

FLOW

"B"

✓ E/340.75
✓ E/341.


022

160



PLAN

1


PLH



SECTION "A-A"



SECTION "B-B"



BOROUGH OF RAMSEY BERGEN COUNTY		NEW JERSEY	
PLAN OF CRYSTAL SPRING LAKE SPILLWAY SHOWING EXISTING CONDITIONS AND MAINTENANCE REQUIREMENTS AT SPILLWAY AND AT ROOF SLAB			
JOB & JOB CONSULTING ENGINEERS 100 HUDSON ST. HACKENSACK, N.J.		DRAWN BY A.S. DATE CHECKED BY K.J. SCALE MAP NO. SHEET 47-36 1 C	
KENNETH G. B. JOB, P.E. PROFESSIONAL ENGINEER N.J. LIC. NO. 1111		DATE 7/11/11	

2

APPENDIX A

CHECK LIST - VISUAL OBSERVATIONS

CHECK LIST - ENGINEERING, CONSTRUCTION
MAINTENANCE DATA

Check List
Visual Inspection
Phase 1

Name Dam Crystal Spring Lake County Bergen State New Jersey Coordinators NJDEP

Coordinates: Lat. 41° 02' 50" N
Long. 79° 08' 06" W

Nov. 30, 1978 &

Date(s) Inspection Jan 4, 1979 Weather Partly Cloudy Temperature 42° F

Pool Elevation at Time of Inspection 349.5' M.S.L. Tailwater at Time of Inspection 342.5' M.S.L.

Inspection Personnel:
(November 30, 1978)

J. A. Bischoff

R. C. Gaffin

D. J. Lachel

T. C. MacDonald

F. L. Panuzio

A. R. Slaughter
P. L. Wagner

(January 4, 1979)
R. J. Jenny

A. L. Slaughter

P. L. Wagner Recorder

Owner Representative:
(November 30, 1978)

Otto M. Cavallo

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SEEPAGE OR LEAKAGE	Not Applicable	
STRUCTURE TO ABUTMENT/EMBANKMENT JUNCTIONS	Not Applicable	
DRAINS	Not Applicable	
WATER PASSAGES	Not Applicable	
FOUNDATION	Not Applicable	

CONCRETE/MASONRY DAMS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS CONCRETE SURFACES	Not Applicable	
STRUCTURAL CRACKING	Not Applicable	
VERTICAL AND HORIZONTAL ALIGNMENT	Not Applicable	
MONOLITH JOINTS	Not Applicable	
CONSTRUCTION JOINTS	Not Applicable	

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	Asphalt roadway along crest of embankment. No surface cracks were observed on crest or face.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	No movement or cracking could be detected. The toe at the downstream side of the dam was extremely uneven due to the unevenness of the face. Marshy area downstream of left side of dam.	
SLOUCHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Very uneven downstream slope with numerous large (3'-6') glacial boulders on surface. Some unevenness undoubtedly due to erosion, including overtopping. Also probably due to tree roots and trash building with time. Upstream slope also uneven, but less so.	Certain areas of downstream embankment are very steep (1:1) and should be graded.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Asphalt roadway on crest appears relatively new. No settlement or horizontal misalignment of the crest could be detected.	
RIPRAP FAILURES	No riprap observed on upstream face. There may have been some dumped rock facing on downstream face at one time, but is now very sporadic.	Riprap should be placed on upstream slope.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
VEGETATION	Numerous large trees and heavy undergrowth cover both upstream and downstream slopes.	Tree roots could endanger core wall and should be removed.
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Abutments are earth, at about same elevation as dam. Junction of the embankment and its abutments and the embankment and the spillway appear to be tight, with no evidence of separation or movement.	Concrete core wall reportedly pierced when utilities were brought to developments on left side of lake.
ANY NOTICEABLE SEEPAGE	Seepage at toe of embankment about 100 ft. from left abutment. Flow 2 to 5 gpm. over a 15-foot length. Water is clear but there is some indication of possible quick conditions. Other seepage ($\pm 1/2$ gpm) at outlet discharge.	Source of seepage should be determined by owner.
STAFF GAGE AND RECORDER	None	
DRAINS	None observed	

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Not Applicable	
INTAKE STRUCTURE	Intake structure was submerged and could not be observed.	
OUTLET STRUCTURE	2 parallel 10-inch outlet pipes, with valves located in a manhole on north side of road 200 feet east of spillway. Manhole filled with water. Outlet pipes on downstream side were hidden by a large stone & debris and could not be observed.	
OUTLET CHANNEL	Outlet empties into shallow, poorly defined ravine tributary to main stream. About 1/2 gpm seepage or leakage at outlet.	
EMERGENCY GATE	The outlet works described above is the emergency gate.	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	Spillway is 2-bay overflow masonry weir separated by bridge deck support pier. Weir appears in generally good condition, with no appreciable erosion of crest or downstream face.	
APPROACH CHANNEL	None	
DISCHARGE CHANNEL	Discharge from masonry spillway apron flows over toe wall into a concrete lined curved channel bordered by vertical masonry and block walls. Both walls and channel appear structurally sound. No erosion or plucking of slab was evident.	
BRIDGE AND PIERS	Bridge over spillway has composite steel and concrete deck with the underside recently gunited. Appears to be in good condition. Masonry block center pier and 2 spillway training walls have been repaired with mortar patching and appear in good condition.	

GATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL	Not Applicable	
APPROACH CHANNEL	Not Applicable	
DISCHARGE CHANNEL	Not Applicable	
BRIDGE AND PIERS	Not Applicable	
GATES AND OPERATION EQUIPMENT	Not Applicable	

INSTRUMENTATION

VISUAL EXAMINATION MONUMENTATION/SURVEYS	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
	None	
OBSERVATION WELLS	None	
WEIRS	None	
PIEZOMETERS	None	
OTHER	None	

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Urban area of large residences on lots of about 1/2 acre with numerous trees on eastern side of reservoir. Golf course on western side. Gentle slopes. Little freeboard between reservoir and top of roadway.	
SEDIMENTATION	Water was clear with no evidence of sedimentation, however, it was reported that it has been necessary to dredge the reservoir.	
DEBRIS	Minor debris at spillway. .	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Lined channel about 100' downstream of spillway. Stream meanders considerably thereafter, area is heavily wooded. Right bank flood plain is residential development.	
SLOPES	Moderate slopes	
APPROXIMATE NO. OF HOUSES AND POPULATION	2 houses immediately downstream of spillway and several on right bank further downstream	High hazard conditions, especially for houses immediately downstream.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	Plan prepared from field measurements made during inspection (See Plate 2)
REGIONAL VICINITY MAP	U.S. Geological Survey map (See Plate 1)
CONSTRUCTION HISTORY	Limited information from owner's files :
TYPICAL SECTIONS OF DAM	Not available
HYDROLOGIC/HYDRAULIC DATA	Computations of spillway capacity available in State files.
OUTLETS - PLAN	Not Available
- DETAILS	Not Available
- CONSTRAINTS	Not Available
- DISCHARGE RATINGS	Not Available
RAINFALL/RESERVOIR RECORDS	Not Available

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
DESIGN REPORTS	Not Available
GEOLOGY REPORTS	Not Available. Reconnaissance made during inspection.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	Not Available
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	Not Available
POST-CONSTRUCTION SURVEYS OF DAM	Have survey of spillway area only (See spillway).
BORROW SOURCES	Not Known

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
SPILLWAY-PLAN -SECTIONS -DETAILS	"Plan of Crystal Spring Lake Spillway, showing existing Conditions and Maintenance Requirements at Spillway and at Roof Slab", July 12, 1976, Scale 1" = 5', by Job and Job, Consulting Engineers (See Plate 3).
OPERATING EQUIPMENT PLANS & DETAILS	Not Available
MONITORING SYSTEMS	None
MODIFICATIONS	Spillway repairs as above.
HIGH POOL RECORDS	Not Available.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	Not Available
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None Reported. Dam has been overtopped.

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM

REMARKS

MAINTENANCE
OPERATION
RECORDS

Not Available.

APPENDIX B
Photographs



Photo 1 - Downstream embankment looking east
from spillway area. (November 30, 1978)



Photo 2 - Seepage (arrow) at downstream toe of embankment near left abutment.
(November 30, 1978)



Photo 3 - Crest of dam and upstream embankment, showing heavy growth of trees. (November 30, 1978)




Photo 4 - Downstream View of Spillway.
(November 30, 1978)



Photo 5 - Flow over portion of rock masonry
spillway weir. (November 30, 1978)



Photo 6 - Reservoir drain outlet obstructed by debris. (November 30, 1978)



Photo 7 - Reservoir area, looking north. (November 30, 1978)



Photo 8 - Concrete weir at end of lined
channel downstream of the spillway.
(November 30, 1978)



Photo 9 - House on right side of lined
channel downstream of spillway.
(November 30, 1978)

APPENDIX C

REGIONAL GEOLOGY - PIEDMONT LOWLANDS

REGIONAL GEOLOGY - PIEDMONT LOWLANDS

Physiography

The Piedmont Lowlands Province of New Jersey lies northwest of a line approximately between Trenton and Perth Amboy and southeast of an approximate line between Milford on the Delaware River and Mahwah near the New York State border. Physiographically, the province is situated between the predominantly Precambrian age New Jersey Highlands Province to the northwest and the typically unconsolidated Cretaceous age and younger sediments of the Coastal Plain Province to the southeast. (See Figure C-1).

Bedrock

The Piedmont Lowlands, encompassing about one-fifth of the state, is characterized by northwestward dipping bedrock composed of interbedded red shales, siltstones and sandstones of Triassic and Jurassic age and igneous basalt extrusions (lava flows) and diabase intrusions of Jurassic age. The sedimentary rocks have been eroded to a broad southeastward sloping piedmont plain. The northwest border of the province is a northeast-southwest trending fault zone (Ramapo Fault) which truncates the sedimentary beds. Total vertical displacement on the fault may reach 10,000 feet.


The gently rolling lowland topography of the piedmont lowlands is pierced by long asymmetric ridges of hard

and resistant igneous rocks which were intruded into or on top of the sedimentary sequences. With the subsequent erosion of the softer sedimentary rocks, these igneous formations have been left standing, often in bold relief, up to 400 ft. above the surrounding plains. The igneous bodies composed of diabase and basalt form the Palisades along the Hudson River and the three Watchung Mountain ridges of the central Piedmont. The ridges are all steeper on the southeast with gentle dip slopes to the northwest.

Overburden

The Pleistocene Age Wisconsin continental glacier has smoothed and filled approximately the northern half of the province. The terminal moraine of the glacier extends from Perth Amboy to Summit then northward to Morris Plains. North of the morainal line the soils characteristically consist of glacial tills overlying the bedrock with scattered overlying stratified outwash deposits. At least three large glacial lakes occupied portions of the area north of the moraine at different periods, resulting in a relatively flat topography composed predominantly of silts and clays.

South of the terminal moraine, most of the overburden consists of alluvial deposits overlying a more highly developed weathered transition zone on top of the bedrock. Some highly weathered tills of pre-Wisconsin glaciation can be found on the top of intervalley ridges. Much of the alluvium is glacial outwash.



SCHEMATIC CROSS-SECTION OF
NEW JERSEY PIEDMONT LOWLANDS
PHYSIOGRAPHIC PROVINCE

JENNY / LEEDSHILL
JANUARY 1979

FIGURE C-1

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

CRYSTAL SPRING LAKE

DRAINAGE AREA CHARACTERISTICS: 1.77 SQ. MI

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 349.3 (65 AF)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): 352.9 (130 AF)

ELEVATION MAXIMUM DESIGN POOL: 355.3

ELEVATION TOP DAM: 352.9

CREST: SPILLWAY

- a. Elevation 349.3
- b. Type CONCRETE WALL
- c. Width 21'
- d. Length 30'
- e. Location Spillover —
- f. Number and Type of Gates NONE

OUTLET WORKS: —

- a. Type 2-10" PIPE
- b. Location —
- c. Entrance inverts 240 HSL
- d. Exit inverts —
- e. Emergency draindown facilities —

HYDROMETEOROLOGICAL GAGES: NONE


- a. Type —
- b. Location —
- c. Records —

MAXIMUM NON-DAMAGING DISCHARGE: 450 CFS

79019

302-03

CRYSTAL SPRING LAKE DAM



CRYSTAL SPRING LAKE

CHAMPION LINE NO. G36-P LEEDS, HILL AND JEWETT, INC.

BY RBE DATE 7/12/20 CLIENT N.J.

SHEET NO. 1 OF 2

CHKD. DATE _____ JOB TIME OF CONCENTRATION

JOB NO. 302

1	2	3	4	5	6	7	8	9
1	DATA							
2		$L = \text{STREAM LENGTH FROM WATERSHED OUTLET TO THE MOST DISTANT RIDGE} = 4.55 \text{ mi.}$						
3								
4		$L_{CA} = \text{STREAM LENGTH FROM BASIN CENTROID} = 1.89 \text{ mi.}$						
5								
6		$H = \text{DIFF BETWEEN ELEV AT OUTLET AND ELEV AT MOST DISTANT POINT} = 540 - 340 = 200 \text{ FT.}$						
7								
8								
9								
10		$T_L = \text{TIME OF CONCENTRATION OR TIME FOR WATER TO FLOW FROM THE MOST DISTANT POINT IN THE WATERSHED TO THE WATERSHED OUTLET}$						
11								
12								
13								
14								

15		$T_L = \text{LAG TIME FROM CENTER OF EXCESS RAINFALL TO TIME OF PEAK.} = 0.6 T_L$						
16								
17								


18	METHOD 1	$T_L = \frac{1.15}{7700 H^{0.38}} \quad \begin{matrix} L \text{ IN FT.} \\ H \text{ IN FT.} \end{matrix}$						
19								
20								
21		$T_L = \frac{0.6 L^{1.15}}{7700 H^{0.38}}$						
22								
23								

24	METHOD 2	$T_L = \left(\frac{11.9 L^3}{H} \right)^{0.385} \quad \begin{matrix} L \text{ IN MILES} \\ H \text{ IN FT.} \end{matrix}$						
25								
26								
27		$T_L = 0.6 \left(\frac{11.9 L^3}{H} \right)^{0.385}$						
28								
29								

30	METHOD 3	$T_L = C_T \left(\frac{L L_C}{S^{1/2}} \right)^{0.38} \quad \begin{matrix} S \text{ IN FT./MI} \\ S = H/L = 0.83\% \end{matrix}$						
31								
32		$T_L = C_T \left(\frac{L L_C}{(H/L)^{1/2}} \right)^{0.38} \quad \begin{matrix} C_T = 1.7 \\ = 0.72 \\ = 0.55 \end{matrix} \quad \begin{matrix} \text{MOUNTAIN} \\ \text{FOOTHILL} \\ \text{VALLEY DRAINAGE} \\ \text{AREA} \end{matrix}$						
33								
34								
35								
36								
37								
38								

39	METHOD 4	$T_L = L/V \quad \begin{matrix} V = \text{AVG VELOCITY FROM CURVE OF V VS. AVG SLOPE} \\ V = 1.4 \text{ FPS} \end{matrix}$						
40								
41		$T_L = 0.6 L/V$						
42								
43								

44	LAG IN HOURS					
45	CRYSTAL	METHODS				
46	SPRING	1	2	3	4	USE
47		1.1	1.2	0.8	2.9	1.1
48			0-3			

$$\frac{1}{2} \sqrt{2}$$


LEEDS, HILL AND JEWETT, INC.

BY P.B.E. DATE CLIENT N.J. DAM SAFETY SHEET NO. OF

CHKD. DATE JOB JOB NO. 302-03

REFERENCES

METHOD 1 - FROM "HANDBOOK OF APPLIED HYDROLOGY"
BY CHOW
MCGRAW HILL PP 21-10, 11

METHOD 2 - FROM CALIFORNIA CULVERTS PRACTICE, CALIF
HIGHWAYS AND PUBLIC WORKS, SEPT 1942
SEE USBR DESIGN OF SMALL DAMS
PG. 71

METHOD 3 - FROM HYDROLOGY FOR ENGINEERS
LINSLEY/KOHLER/PAULIUS 1975
PP. 247-248

METHOD 4 - FROM U.S. NAVY - TECHNICAL PUBLICATION
NAVDOKS TP-PW-5 TABLE 8B, MARCH 1953
SEE USBR DESIGN OF SMALL DAMS PG. 70

ID-5

RBE

7B(221

CRYSTAL SPRING

302.03


1/2

OVER SPILLWAY $C = 2.9$ FROM DATA (SEE EAST SHEET)OVER BRIDGE $C = 2.6$ BROADCASTED WEIRGRASSY FLOW $C = 0.61$ COMPARISON OF CASE WITH MODEL
(MODEL A) IN KINGS HANDBOOK
TABLE 4-8, AVG VALUE OVER RANGE
CONSIDERED

$$Q = CLH^{1.5}$$

$$Q = C_e d \sqrt{2gH - d} L$$

$$L = 30'$$



$$d = 1.89$$

H (Ft)	C	Q (CFS)
0		0
0.5		31
1.0	2.9	87
1.5		160
1.89		226
1.89		270
2.0		285
2.2		311
2.5	0.61	346
3.0		398
3.6		453
3.6		453
4.0		505
4.5	0.61	590
5.0	+	688
6.0	2.6	914
8.0		1457

SAMPLE $H = 4.0$

$$Q = (0.61) \sqrt{(4 - 1.89) 2g} (30)(1.89) + (4 - 3.6)^{1.5} 30(2.6)$$

$$Q = 505 \text{ CFS}$$

D-6

U. Lachner, 1952

TABLE 5-6. VALUES OF THE ROUGHNESS COEFFICIENT n (continued)

Type of channel and description	Minimum	Normal	Maximum
C. EXCAVATED OR DREDGED			
a. Earth, straight and uniform			
1. Clean, recently completed	0.016	0.018	0.020
2. Clean, after weathering	0.018	0.022	0.025
3. Gravel, uniform section, clean	0.022	0.025	0.030
4. With short grass, few weeds	0.022	0.027	0.033
b. Earth, winding and sluggish			
1. No vegetation	0.023	0.025	0.030
2. Grass, some weeds	0.025	0.030	0.033
3. Dense weeds or aquatic plants in deep channels	0.030	0.035	0.040
4. Earth bottom and rubble sides	0.028	0.030	0.035
5. Stony bottom and weedy banks	0.025	0.035	0.040
6. Cobble bottom and clean sides	0.030	0.040	0.050
c. Dragline-excavated or dredged			
1. No vegetation	0.025	0.028	0.033
2. Light brush on banks	0.035	0.050	0.060
d. Rock cuts			
1. Smooth and uniform	0.025	0.035	0.040
2. Jagged and irregular	0.035	0.040	0.050
e. Channels not maintained, weeds and brush uncut			
1. Dense weeds, high as flow depth	0.050	0.080	0.120
2. Clean bottom, brush on sides	0.040	0.050	0.080
3. Same, highest stage of flow	0.045	0.070	0.110
4. Dense brush, high stage	0.080	0.100	0.140
D. NATURAL STREAMS			
D-1. Minor streams (top width at flood stage <100 ft)			
a. Streams on plain			
1. Clean, straight, full stage, no rills or deep pools	0.025	0.030	0.033
2. Same as above, but more stones and weeds	0.030	0.035	0.040
3. Clean, winding, some pools and shoals	0.033	0.040	0.045
4. Same as above, but some weeds and stones	0.035	0.045	0.050
5. Same as above, lower stages, more ineffective slopes and sections	0.040	0.048	0.055
6. Same as 4, but more stones	0.045	0.050	0.060
7. Sluggish reaches, weedy, deep pools	0.050	0.070	0.080
8. Very weedy reaches, deep pools, or floodways with heavy stand of timber and underbrush	0.075	0.100	0.150

STATION 3,4, & 5

TABLE 5-4. VALUES OF THE ROUGHNESS COEFFICIENT n (continued)

Type of channel and description	Minimum	Normal	Maximum
b. Mountain streams, no vegetation in channel, banks usually steep, trees and brush along banks submerged at high stages			
1. Bottom: gravels, cobbles, and few boulders	0.030	0.040	0.050
2. Bottom: cobbles with large boulders	0.040	0.050	0.070
D-2. Flood plains			
a. Pasture, no brush			
1. Short grass	0.025	0.030	0.035
2. High grass	0.030	0.035	0.050
b. Cultivated areas			
1. No crop	0.020	0.030	0.040
2. Mature row crops	0.025	0.035	0.045
3. Mature field crops	0.030	0.040	0.050
c. Brush			
1. Scattered brush, heavy weeds	0.035	0.050	0.070
2. Light brush and trees, in winter	0.035	0.050	0.060
3. Light brush and trees, in summer	0.010	0.060	0.080
4. Medium to dense brush, in winter	0.045	0.070	0.110
5. Medium to dense brush, in summer	0.070	0.100	0.160
d. Trees			
1. Dense willows, summer, straight	0.110	0.150	0.200
2. Cleared land with tree stumps, no sprouts	0.030	0.040	0.050
3. Same as above, but with heavy growth of sprouts	0.050	0.060	0.080
4. Heavy stand of timber, a few down trees, little undergrowth, flood stage below branches	0.080	0.100	0.120
5. Same as above, but with flood stage reaching branches	0.100	0.120	0.160
D-3. Major streams (top width at flood stage >100 ft). The n value is less than that for minor streams of similar description, because banks offer less effective resistance.			
a. Regular section with no boulders or brush	0.025	0.060
b. Irregular and rough section	0.035	0.100

OPEN-CHANNEL HYDRAULICS

STATION 3 & 4


VEN TE CHOW, Ph.D.
Professor of Hydraulic Engineering
University of Illinois

PR. 70213

302-03

CRYSTAL SPRINGS

LOCATION MAP OF CROSS-SECTIONS
USED IN ROUTING



RBE

790213

CRYSTAL SPRINGS DAM

302-03

ASSUMED BREACH PARAMETERS

WIDTH OF BREACH BOTTOM: 270

SIDE SLOPES: VERTICAL

BREACH BOTTOM ELEV.: 340

TIME TO FAIL: 4.0 hrs

ELEV. @ WHICH FAILURE OCCURS: 352.9 FT

INITIAL WATER SURFACE ELEV.: 349.3 FT

11 BASED ON PREVIOUS STUDIES OF ACTUAL DAM FAILURES.

Jm

790110

Crystal Springs

302-03

Reservoir Drawdown Time

ASSUME ORIFICE EQUATION
WITH NO TAILWATER, AND NO INFLUWS INTO
THE RESERVOIR.

$$Q = CA\sqrt{2gh}$$

For 1-8" & 1-12", $A = 1.13 \text{ ft}^2$

For 2-10" $A = 1.09 \text{ ft}^2 \leftarrow \text{USE}$

Assume $C = 0.6$

$$Q = 0.6 \times 1.09 \times \sqrt{2g} \times H^{1/2}$$

$$Q = 5.25 H^{1/2}$$

Elev, ft	Sto	ΔSto	Avg h	Avg Q cfs	Drain Minutes	ΣDrain Hours
340	0					
		20 AF	6.8	13.69	17.7	17.7
345	20					
		15 AF	3.3	9.54	19.0	36.7
347	35					
		30 AF	1.15	5.63	64.5	101.2
→ 349.3	65					
[spillway						

$$\frac{101.2}{24} = 4.2 \text{ days}$$

-208-

JOB SPECIFICATION

NPLAN= 1 NRTIO= 4 LRTIO= 1

15 1-50 1-90

.....

SUB-AREA RUNOFF COMPUTATION

THE: ON WAYGROH TO RESERV010

TESTAO	Y-ONB	YECOM	YTAGF	YDIT	YNAME	YSPACE	YAUTO
1							
2							
3							
4							
5							
6							
7							
8							
9							
10							
11							
12							
13							
14							
15							
16							
17							
18							
19							
20							
21							
22							
23							
24							
25							
26							
27							
28							
29							
30							
31							
32							
33							
34							
35							
36							
37							
38							
39							
40							
41							
42							
43							
44							
45							
46							
47							
48							
49							
50							
51							
52							
53							
54							
55							
56							
57							
58							
59							
60							
61							
62							
63							
64							
65							
66							
67							
68							
69							
70							
71							
72							
73							
74							
75							
76							
77							
78							
79							
80							
81	</						

HYDROGRAPHIC DATA

[illegible]

PRECISE DATA

SPFE	PMS	R6	R12	R24	R48	R72	R96
SPFE	PMS	R6	R12	R24	R48	R72	R96

00:00
-000
TASAC COMPLETED BY THE PROGRAM YC
33

1055 012A

1055 0070

UNIT HYDROGRAPH DATA

TC= 0.00 LAS= 1.10

```

STERO= -1.00      ORCSM=  -.05      ERROR= 2.00
RECESSION DATA

```

SECRET

UNIT HYDROGRAPH 24 END OF PERIOD ORDINATES, IC= 0.00 HOURS, LAG= 1.10 VOL= 1.00

72.	226.	474.	656.	697.	637.	525.	360.	257.	105.
-----	------	------	------	------	------	------	------	------	------

135.	96.	69.	49.	35.	25.	16.	13.	9.	7.
------	-----	-----	-----	-----	-----	-----	-----	----	----

1.
2.
3.
4.

[The page contains extremely faint, illegible text, likely bleed-through from the reverse side.]

1

1

Downloaded from <http://ajph.org/> on June 11, 2015

NO. DA	HR. MM	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW COMP Q	NO. DA	HR. MM	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW COMP Q
1.01	1.15	1	.01	0.00	.03	2.	1.01	12.15	49	.49	.45	.04	257.
1.01	1.30	2	.03	0.00	.03	2.	1.01	12.30	50	.49	.45	.04	257.
1.01	1.45	3	.03	0.00	.03	1.	1.01	12.45	51	.49	.45	.04	257.
1.01	1.00	4	.03	0.00	.03	1.	1.01	13.00	52	.49	.45	.04	257.
1.01	1.15	5	.03	0.00	.03	1.	1.01	13.15	53	.59	.55	.04	1088.
1.01	1.30	6	.03	0.00	.03	1.	1.01	13.30	54	.59	.55	.04	1088.
1.01	1.45	7	.03	0.00	.03	1.	1.01	13.45	55	.59	.55	.04	1088.
1.01	2.00	8	.03	0.00	.03	1.	1.01	13.00	56	.59	.55	.04	1088.
1.01	2.15	9	.03	0.00	.03	1.	1.01	13.15	57	.73	.70	.04	1088.
1.01	2.30	10	.03	0.00	.03	1.	1.01	13.30	58	.73	.70	.04	1088.
1.01	2.45	11	.03	0.00	.03	1.	1.01	13.45	59	.73	.70	.04	1088.
1.01	3.00	12	.03	0.00	.03	1.	1.01	14.00	60	.73	.70	.04	1088.
1.01	3.15	13	.03	0.00	.03	1.	1.01	14.15	61	.73	.70	.04	1088.
1.01	3.30	14	.03	0.00	.03	1.	1.01	14.30	62	.73	.70	.04	1088.
1.01	3.45	15	.03	0.00	.03	1.	1.01	14.45	63	.73	.70	.04	1088.
1.01	4.00	16	.03	0.00	.03	1.	1.01	15.00	64	.73	.70	.04	1088.
1.01	4.15	17	.03	0.00	.03	1.	1.01	15.15	65	.73	.70	.04	1088.
1.01	4.30	18	.03	0.00	.03	1.	1.01	15.30	66	.73	.70	.04	1088.
1.01	4.45	19	.03	0.00	.03	1.	1.01	15.45	67	.73	.70	.04	1088.
1.01	5.00	20	.03	0.00	.03	1.	1.01	16.00	68	.73	.70	.04	1088.
1.01	5.15	21	.03	0.00	.03	1.	1.01	16.15	69	.73	.70	.04	1088.
1.01	5.30	22	.03	0.00	.03	1.	1.01	16.30	70	.73	.70	.04	1088.
1.01	5.45	23	.03	0.00	.03	1.	1.01	16.45	71	.73	.70	.04	1088.
1.01	6.00	24	.03	0.00	.03	1.	1.01	17.00	72	.73	.70	.04	1088.
1.01	6.15	25	.03	0.00	.03	1.	1.01	17.15	73	.73	.70	.04	1088.
1.01	6.30	26	.03	0.00	.03	1.	1.01	17.30	74	.73	.70	.04	1088.
1.01	6.45	27	.03	0.00	.03	1.	1.01	17.45	75	.73	.70	.04	1088.
1.01	7.00	28	.03	0.00	.03	1.	1.01	18.00	76	.73	.70	.04	1088.
1.01	7.15	29	.03	0.00	.03	1.	1.01	18.15	77	.73	.70	.04	1088.
1.01	7.30	30	.03	0.00	.03	1.	1.01	18.30	78	.73	.70	.04	1088.
1.01	7.45	31	.03	0.00	.03	1.	1.01	18.45	79	.73	.70	.04	1088.
1.01	8.00	32	.03	0.00	.03	1.	1.01	19.00	80	.73	.70	.04	1088.
1.01	8.15	33	.03	0.00	.03	1.	1.01	19.15	81	.73	.70	.04	1088.
1.01	8.30	34	.03	0.00	.03	1.	1.01	19.30	82	.73	.70	.04	1088.
1.01	8.45	35	.03	0.00	.03	1.	1.01	19.45	83	.73	.70	.04	1088.
1.01	9.00	36	.03	0.00	.03	1.	1.01	20.00	84	.73	.70	.04	1088.
1.01	9.15	37	.03	0.00	.03	1.	1.01	20.15	85	.73	.70	.04	1088.
1.01	9.30	38	.03	0.00	.03	1.	1.01	20.30	86	.73	.70	.04	1088.
1.01	9.45	39	.03	0.00	.03	1.	1.01	20.45	87	.73	.70	.04	1088.
1.01	10.00	40	.03	0.00	.03	1.	1.01	21.00	88	.73	.70	.04	1088.
1.01	10.15	41	.03	0.00	.03	1.	1.01	21.15	89	.73	.70	.04	1088.
1.01	10.30	42	.03	0.00	.03	1.	1.01	21.30	90	.73	.70	.04	1088.
1.01	10.45	43	.03	0.00	.03	1.	1.01	21.45	91	.73	.70	.04	1088.
1.01	11.00	44	.03	0.00	.03	1.	1.01	22.00	92	.73	.70	.04	1088.
1.01	11.15	45	.03	0.00	.03	1.	1.01	22.15	93	.73	.70	.04	1088.
1.01	11.30	46	.03	0.00	.03	1.	1.01	22.30	94	.73	.70	.04	1088.
1.01	11.45	47	.03	0.00	.03	1.	1.01	22.45	95	.73	.70	.04	1088.
1.01	12.00	48	.03	0.00	.03	1.	1.01	23.00	96	.73	.70	.04	1088.
1.01	12.15	49	.03	0.00	.03	1.	1.01	23.15	97	.73	.70	.04	1088.
1.01	12.30	50	.03	0.00	.03	1.	1.01	23.30	98	.73	.70	.04	1088.
1.01	12.45	51	.03	0.00	.03	1.	1.01	23.45	99	.73	.70	.04	1088.
1.01	13.00	52	.03	0.00	.03	1.	1.01	24.00	100	.73	.70	.04	1088.

SUM 23.41 13.55 3.45 987.40
 1 595.14 496.11 90.1 (2569.47)

PEAK
 614.2
 17.4
 17.4

CFS
 17.4
 17.4

INCHES
 17.4
 17.4

THOUS CU FT
 17.4
 17.4

72-HOUR
 965.
 27.
 19.86

24-HOUR
 945.
 27.
 19.86

8-HOUR
 311.
 9.
 44.96

LOSS
 17.4
 17.4
 17.4

END-OF-PERIOD FLOW
 906.2
 256.2
 586.39

TOTAL VOLUME
 906.2
 256.2
 586.39

STATION 2. PLAN 1. RATIO %
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW		STORAGE		STAGE	
0.	1.	0.	1.	0.	1.
0.	1.	0.	1.	0.	1.
1.	1.	1.	1.	1.	1.
2.	1.	1.	1.	1.	1.
3.	1.	1.	1.	1.	1.
4.	1.	1.	1.	1.	1.
5.	1.	1.	1.	1.	1.
6.	1.	1.	1.	1.	1.
7.	1.	1.	1.	1.	1.
8.	1.	1.	1.	1.	1.
9.	1.	1.	1.	1.	1.
10.	1.	1.	1.	1.	1.
11.	1.	1.	1.	1.	1.
12.	1.	1.	1.	1.	1.
13.	1.	1.	1.	1.	1.
14.	1.	1.	1.	1.	1.
15.	1.	1.	1.	1.	1.
16.	1.	1.	1.	1.	1.
17.	1.	1.	1.	1.	1.
18.	1.	1.	1.	1.	1.
19.	1.	1.	1.	1.	1.
20.	1.	1.	1.	1.	1.
21.	1.	1.	1.	1.	1.
22.	1.	1.	1.	1.	1.
23.	1.	1.	1.	1.	1.
24.	1.	1.	1.	1.	1.
25.	1.	1.	1.	1.	1.
26.	1.	1.	1.	1.	1.
27.	1.	1.	1.	1.	1.
28.	1.	1.	1.	1.	1.
29.	1.	1.	1.	1.	1.
30.	1.	1.	1.	1.	1.
31.	1.	1.	1.	1.	1.
32.	1.	1.	1.	1.	1.
33.	1.	1.	1.	1.	1.
34.	1.	1.	1.	1.	1.
35.	1.	1.	1.	1.	1.
36.	1.	1.	1.	1.	1.
37.	1.	1.	1.	1.	1.
38.	1.	1.	1.	1.	1.
39.	1.	1.	1.	1.	1.
40.	1.	1.	1.	1.	1.
41.	1.	1.	1.	1.	1.
42.	1.	1.	1.	1.	1.
43.	1.	1.	1.	1.	1.
44.	1.	1.	1.	1.	1.
45.	1.	1.	1.	1.	1.
46.	1.	1.	1.	1.	1.
47.	1.	1.	1.	1.	1.
48.	1.	1.	1.	1.	1.
49.	1.	1.	1.	1.	1.
50.	1.	1.	1.	1.	1.
51.	1.	1.	1.	1.	1.
52.	1.	1.	1.	1.	1.
53.	1.	1.	1.	1.	1.
54.	1.	1.	1.	1.	1.
55.	1.	1.	1.	1.	1.
56.	1.	1.	1.	1.	1.
57.	1.	1.	1.	1.	1.
58.	1.	1.	1.	1.	1.
59.	1.	1.	1.	1.	1.
60.	1.	1.	1.	1.	1.
61.	1.	1.	1.	1.	1.
62.	1.	1.	1.	1.	1.
63.	1.	1.	1.	1.	1.
64.	1.	1.	1.	1.	1.
65.	1.	1.	1.	1.	1.
66.	1.	1.	1.	1.	1.
67.	1.	1.	1.	1.	1.
68.	1.	1.	1.	1.	1.
69.	1.	1.	1.	1.	1.
70.	1.	1.	1.	1.	1.
71.	1.	1.	1.	1.	1.
72.	1.	1.	1.	1.	1.
73.	1.	1.	1.	1.	1.
74.	1.	1.	1.	1.	1.
75.	1.	1.	1.	1.	1.
76.	1.	1.	1.	1.	1.
77.	1.	1.	1.	1.	1.
78.	1.	1.	1.	1.	1.
79.	1.	1.	1.	1.	1.
80.	1.	1.	1.	1.	1.
81.	1.	1.	1.	1.	1.
82.	1.	1.	1.	1.	1.
83.	1.	1.	1.	1.	1.
84.	1.	1.	1.	1.	1.
85.	1.	1.	1.	1.	1.
86.	1.	1.	1.	1.	1.
87.	1.	1.	1.	1.	1.
88.	1.	1.	1.	1.	1.
89.	1.	1.	1.	1.	1.
90.	1.	1.	1.	1.	1.
91.	1.	1.	1.	1.	1.
92.	1.	1.	1.	1.	1.
93.	1.	1.	1.	1.	1.
94.	1.	1.	1.	1.	1.
95.	1.	1.	1.	1.	1.
96.	1.	1.	1.	1.	1.
97.	1.	1.	1.	1.	1.
98.	1.	1.	1.	1.	1.
99.	1.	1.	1.	1.	1.
100.	1.	1.	1.	1.	1.

PEAK OUTFLOW IS 6131. AT TIME 16.75 HOURS

CFS	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
6131.	6131.	3293.	931.	931.	8803.
INCHES	176.	93.	26.	26.	2512.
AC-FT	44.21	17.33	19.58	19.58	19.58
THOUS CU M	1835.	1067.	1067.	1067.	1067.
	2017.	2276.	2276.	2276.	2276.

CLASS	CLOS	ISAO	RECOMP	RECOM	ITAVE	JPLT	JPRP	INAME	ESTAGE	IAUDD
0.0	0.000	3	1	ROUTING DATA		0	0		1	0
			AVE	INRES	ESTAGE	IOPT	IPMP		LSFR	
			0.00	1	1	0			0	
								STORA	ESPRAT	
				LAS	ASINR	0.00	TKS	0.000	0	
			MSDOL	0						
			1	0						
			MSDPS							

GM(1)	GM(2)	GM(3)	ELMVT	ELMAX	RLNTH	SEL
.1650	.1450	.1000	338.0	360.0	30.	.01000

GROSS
SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC
\$CD\$
0.00
362.00
190.00
350.60
07.80
00.00
340.00
342.00
1009.00
350.00
150.00
300.00

STORAGE	0.00	0.23	0.44	0.18	0.44	1.33	1.06	2.73	3.62
OUTFLOW	4.44	5.77	6.45	6.16	9.43	12.14	13.35	15.52	15.52
INFLOW	0.47	74.40	239.51	576.77	1248.77	4251.13	4767.17	11101.42	13347.25
STAGE	15343.11	24473.46	34723.18	43691.47	55282.66	77821.24	91137.38	106647.42	121101.62
STAGE	336.40	339.14	343.32	344.47	343.79	344.93	346.11	347.24	348.42
STAGE	349.98	350.74	351.48	352.05	352.41	352.57	352.68	352.73	352.73
STAGE	0.44	74.40	239.51	576.77	1248.77	4251.13	4767.17	11101.42	13347.25
STAGE	15343.11	24473.46	34723.18	43691.47	55282.66	77821.24	91137.38	106647.42	121101.62

[illegible]

HYDROGRAPH ROUTING

CHANNEL ROUTING - MODIFIED PULS- STATION 3 TO 4

ESTAG	ICOMP	SECON	ITAPE	JPLT	JPRT	ISAME	ISTAGE	IAUTO
0.0	0.000	0.00	1	0	0	1	0	0
ROUTING DATA								
IRSS	ISAME	IOPT	IPMP				LSTR	
0.0	0.00	1	0					
MSIPS	MSIOL	LAG	AMSKK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	6.	0	

NORMAL DEPTH CHANNEL ROUTING

QW121	QW121	ELHVT	ELMAX	ELMTH	SEL
0.1000	0.450	310.0	330.0	3450.	.00710

CROSS SECTION COORDINATES--STA.ELEV, STAGE.ELEV--ETC

	0.00	325.00	400.00	520.00	550.00	580.00	600.00	610.00	620.00	630.00
STORAGE	0.00	262.65	417.75	507.90	572.56	615.30	645.49	668.70	685.49	695.13
OUTFLOW	0.00	157.93	192.16	215.93	231.51	241.55	246.39	247.47	246.25	242.26
STAGE	310.00	311.09	312.11	312.16	312.16	312.16	312.26	312.32	312.37	312.40
FLOW	0.00	157.93	215.93	231.51	241.55	246.39	247.47	246.25	242.26	237.20

[illegible]

MAXIMUM STORAGE - 103.

MAXIMUM STAGE IS 317.7

HYDROGRAPH ROUTING

CHANNEL ROUTING - MODIFIED PULS- STATION 4 TO 5

ISTAG	ICOMP	ICOM	ITAPE	JPLT	JPRI	INAME	ISTAGE	IAUTO
1	1	0	0	0	0	1	0	0
ROUTING DATA								
QLOSS	CLOSS	AVG	IRRES	ISAME	ICPT	IPHP	LSTR	
0.0	0.000	0.00	1	1	0	0	0	
MSIPS	MSIOL	LAG	ANSKK	X	TSK	STOMA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.	0	

NORMAL DEPTH CHANNEL ROUTING

CH11	CH12	CH13	ELHVI	ELMAX	ELMTM	SEL
.0308	.0450	.0500	246.0	300.0	246.0	.01000

CROSS SECTION COORDINATES--STA=ELEV, STA=ELEV--ETC
 0+00 303.00 250.00 290.00 375.00 286.00 375.00 286.00 425.00 286.00
 425+00 286.00 400.00 290.00 375.00 286.00 300.00

STORAGE	0+00	2+03	4+06	6+46	15+54	33+59	59+55	88+50	119+44	153+58
	186.71	228.24	269.16	312.47	358.17	406.27	456.76	508.64	562.92	622.59
OUTFLOW	0+00	2+03	4+06	6+46	15+54	33+59	59+55	88+50	119+44	153+58
	2567.83	3331.33	4207.11	5185.13	6274.18	7473.24	8793.98	10229.51	11787.14	134713.29
STAGE	0+00	2+03	4+06	6+46	15+54	33+59	59+55	88+50	119+44	153+58
	286.00	286.74	287.67	288.21	288.93	289.68	290.42	291.16	291.89	292.63
	293.37	294.11	294.84	295.58	296.32	297.05	297.79	298.53	299.26	300.00
FLOW	0+00	2+03	4+06	6+46	15+54	33+59	59+55	88+50	119+44	153+58
	2567.83	3331.33	4207.11	5185.13	6274.18	7473.24	8793.98	10229.51	11787.14	134713.29

3. PLAN 2. RTIO 4

MAXIMUM STAGE IS	290.0
------------------	-------

MAXIMUM STORAGE • 670

MAXIMUM STAGE IS	290.0
------------------	-------

No BREACH

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	1	RATIO	2	RATIO	3	RATIO	4	RATIOS APPLIED TO FLOWS	
												RATIO	RATIO
						.10	.15	.50					1.00
HYDROGRAPH AT													
	1	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
	2	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
ROUTED TO													
	3	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
	4	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
ROUTED TO													
	5	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
	6	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
ROUTED TO													
	7	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77
	8	1.77	1	1.77	1	1.77	1.77	1.77	1.77	1.77	1.77	1.77	1.77

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

PLAN 1
 ELEVATION
 STORAGE
 OUTFLOW

INITIAL VALUE
 346.30
 63.
 0.

SPILLWAY CREST
 347.30
 63.
 0.

TOP OF DAM
 352.00
 112.
 430.

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

TIME OF
 MAX OUTFLOW
 HOURS

TIME OF
 FAILURE
 HOURS

AD-A069 594

NEW JERSEY STATE DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/2
NATIONAL DAM SAFETY PROGRAM. CRYSTAL SPRING LAKE (NJ 00231), PA--ETC(U)
MAY 79 R J JENNY



DACW61-78-C-0124

NL

UNCLASSIFIED

2 OF 2

AD
A069594



END
DATE
FILMED

7 -79

DDC

NEW JERSEY OAN SAFETY - CRYSTAL SPRING LAKE DAM I.O. NO. 00231
HYDRAULIC-HYDROLOGIC ANALYSIS 302-33
PROBABLE MAXIMUM FLOOD

-R82-

JOB SPECIFICATION									
NO	HMR	MIN	IDAY	IMR	IMIN	MEYR	IPLT	IPRT	MSIAN
96	0	15	0	0	0	0	0	0	0
			JOPER			LMPT	TRACE		
			5			0	0		

MULTI-PLAN ANALYSES TO BE PERFORMED

WPLAN= 1 HATIO= 4 LRTIO= 1

RTIOS= .10 .15 .52 1.03

SUB-AREA FLOOD COMPUTATION

INFLCH HYDROGRAPH TO RESERVOIR

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTC
1	0	0	0	0	0	1	0	0

INTVC	IUNG	FACIA	SWAP	TRSPA	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	2	1.77	0.00	1.77	0.00	0.000	0	1	0

PRECIP DATA

SPTE	PMS	MS	R12	R24	R48	R72	R96
0.00	22.00	111.00	123.00	133.00	0.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .000

LOSS DATA

LRMPT	STRGR	OLTHR	RTIOI	ERAIN	STAKS	RTIOK	STRTL	CNSIL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	5.00	1.00	1.50	.15	0.00	0.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= 1.10

RECESSION DATA

STRTO= -1.00 QUESH= -.05 RTIOI= 2.00

UNIT HYDROGRAPH 2% END OF PERIOD ORIGINATES, TC= 0.00 HOURS, LAG= 1.10 VOL= 1.00									
72.	25.	67.	65.	67.	637.	529.	366.	1.10	195.
135.	94.	69.	44.	35.	25.	10.	13.	9.	7.
9.	4.	2.	1.						

NO. DA	HR. IN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLOW COMP Q	NO. DA	HR. IN	PERIOD	RAIN	EXCS	LOSS	COMP Q
1.01	1.35	1	0.3	0.30	0.3	2	1.01	12.15	99	0.9	0.5	0.5	237
1.01	1.30	2	0.3	0.31	0.3	2	1.01	12.30	51	0.9	0.5	0.5	240
1.01	1.45	3	0.3	0.33	0.3	1	1.01	12.45	51	0.9	0.5	0.5	243
1.01	1.00	4	0.3	0.38	0.3	1	1.01	13.00	52	0.9	0.5	0.5	246
1.01	1.15	5	0.3	0.38	0.3	1	1.01	13.15	53	0.9	0.5	0.5	249
1.01	1.30	6	0.3	0.38	0.3	1	1.01	13.30	54	0.9	0.5	0.5	252
1.01	1.45	7	0.3	0.38	0.3	1	1.01	13.45	55	0.9	0.5	0.5	255
1.01	2.00	8	0.3	0.39	0.3	1	1.01	13.00	56	0.9	0.5	0.5	258
1.01	2.15	9	0.3	0.39	0.3	1	1.01	13.15	57	0.9	0.5	0.5	261
1.01	2.30	10	0.3	0.39	0.3	1	1.01	13.30	58	0.9	0.5	0.5	264
1.01	2.45	11	0.3	0.39	0.3	1	1.01	13.45	59	0.9	0.5	0.5	267
1.01	3.00	12	0.3	0.39	0.3	1	1.01	13.00	60	0.9	0.5	0.5	270
1.01	3.15	13	0.3	0.39	0.3	1	1.01	13.15	61	0.9	0.5	0.5	273
1.01	3.30	14	0.3	0.39	0.3	1	1.01	13.30	62	0.9	0.5	0.5	276
1.01	3.45	15	0.3	0.39	0.3	1	1.01	13.45	63	0.9	0.5	0.5	279
1.01	4.00	16	0.3	0.39	0.3	1	1.01	14.00	64	0.9	0.5	0.5	282
1.01	4.15	17	0.3	0.39	0.3	1	1.01	14.15	65	0.9	0.5	0.5	285
1.01	4.30	18	0.3	0.39	0.3	1	1.01	14.30	66	0.9	0.5	0.5	288
1.01	4.45	19	0.3	0.39	0.3	1	1.01	14.45	67	0.9	0.5	0.5	291
1.01	5.00	20	0.3	0.39	0.3	1	1.01	15.00	68	0.9	0.5	0.5	294
1.01	5.15	21	0.3	0.39	0.3	1	1.01	15.15	69	0.9	0.5	0.5	297
1.01	5.30	22	0.3	0.39	0.3	1	1.01	15.30	70	0.9	0.5	0.5	300
1.01	5.45	23	0.3	0.39	0.3	1	1.01	15.45	71	0.9	0.5	0.5	303
1.01	6.00	24	0.3	0.39	0.3	1	1.01	16.00	72	0.9	0.5	0.5	306
1.01	6.15	25	0.3	0.39	0.3	1	1.01	16.15	73	0.9	0.5	0.5	309
1.01	6.30	26	0.3	0.39	0.3	1	1.01	16.30	74	0.9	0.5	0.5	312
1.01	6.45	27	0.3	0.39	0.3	1	1.01	16.45	75	0.9	0.5	0.5	315
1.01	7.00	28	0.3	0.39	0.3	1	1.01	17.00	76	0.9	0.5	0.5	318
1.01	7.15	29	0.3	0.39	0.3	1	1.01	17.15	77	0.9	0.5	0.5	321
1.01	7.30	30	0.3	0.39	0.3	1	1.01	17.30	78	0.9	0.5	0.5	324
1.01	7.45	31	0.3	0.39	0.3	1	1.01	17.45	79	0.9	0.5	0.5	327
1.01	8.00	32	0.3	0.39	0.3	1	1.01	18.00	80	0.9	0.5	0.5	330
1.01	8.15	33	0.3	0.39	0.3	1	1.01	18.15	81	0.9	0.5	0.5	333
1.01	8.30	34	0.3	0.39	0.3	1	1.01	18.30	82	0.9	0.5	0.5	336
1.01	8.45	35	0.3	0.39	0.3	1	1.01	18.45	83	0.9	0.5	0.5	339
1.01	9.00	36	0.3	0.39	0.3	1	1.01	19.00	84	0.9	0.5	0.5	342
1.01	9.15	37	0.3	0.39	0.3	1	1.01	19.15	85	0.9	0.5	0.5	345
1.01	9.30	38	0.3	0.39	0.3	1	1.01	19.30	86	0.9	0.5	0.5	348
1.01	9.45	39	0.3	0.39	0.3	1	1.01	19.45	87	0.9	0.5	0.5	351
1.01	10.00	40	0.3	0.39	0.3	1	1.01	20.00	88	0.9	0.5	0.5	354
1.01	10.15	41	0.3	0.39	0.3	1	1.01	20.15	89	0.9	0.5	0.5	357
1.01	10.30	42	0.3	0.39	0.3	1	1.01	20.30	90	0.9	0.5	0.5	360
1.01	10.45	43	0.3	0.39	0.3	1	1.01	20.45	91	0.9	0.5	0.5	363
1.01	11.00	44	0.3	0.39	0.3	1	1.01	21.00	92	0.9	0.5	0.5	366
1.01	11.15	45	0.3	0.39	0.3	1	1.01	21.15	93	0.9	0.5	0.5	369
1.01	11.30	46	0.3	0.39	0.3	1	1.01	21.30	94	0.9	0.5	0.5	372
1.01	11.45	47	0.3	0.39	0.3	1	1.01	21.45	95	0.9	0.5	0.5	375
1.01	12.00	48	0.3	0.39	0.3	1	1.01	22.00	96	0.9	0.5	0.5	378

SUM 23.41 19.95 3.46 217.2

(595.11 430.11 90.11 2569.57)

PEAK
6-HOUR 3311.
24-HOUR 965.
72-HOUR 27.
TOTAL VOLUME 5682.
CFS 96.
INCHES 17.4.
AC-FT 461.94
THOUS CU FT 1874.
2311.

HYDROGRAPH AT STA 1 FOR PLAN 1, REIO 4									
2-	1-	1-	1-	1-	1-	1-	1-	1-	1-
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
197.	213.	213.	213.	213.	213.	213.	213.	213.	213.
1300.	1300.	1300.	1300.	1300.	1300.	1300.	1300.	1300.	1300.
2071.	2071.	2071.	2071.	2071.	2071.	2071.	2071.	2071.	2071.
3592.	3592.	3592.	3592.	3592.	3592.	3592.	3592.	3592.	3592.
4019.	4019.	4019.	4019.	4019.	4019.	4019.	4019.	4019.	4019.
421.	421.	421.	421.	421.	421.	421.	421.	421.	421.
311.	311.	311.	311.	311.	311.	311.	311.	311.	311.
154.	154.	154.	154.	154.	154.	154.	154.	154.	154.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
 6153. 3311. 945. 945.
 174. 94. 174. 174.
 17.40 51.20 51.20 51.20
 411.20 51.20 51.20 51.20
 1074. 2311. 2311. 2311.
 2025. 2311. 2311. 2311.

D-28

HYDROGRAPH ROUTING

ROUTED FLOWS THROUGH RESERVOIR

ISTAQ	ICMIF	IECON	ITAPE	JPLT	JPAT	INAME	ISTAGE	IAUTO
2	1	0	0	0	0	1	1	0
GLSS	CLSS	AUC	IMES	ISAME	IOPT	IPHP	LSTR	
0.0	0.00	0.00	1	1	0	0	0	
MSIPS	MSIBL	LAG	ANSK	X	TK	STORA	ISPRAY	
1	0	0	0.00	0.00	0.00	05.	-1	
STAGE	349.30	350.30	351.10	351.20	351.30	352.30	352.30	352.30
355.30	357.30	357.30	357.30	357.30	357.30	357.30	357.30	357.30
FLOW	0.00	05.00	160.00	255.00	270.00	205.00	400.00	450.00
915.00	1055.00	1055.00	1055.00	1055.00	1055.00	1055.00	1055.00	1055.00
CAPACITY	0.	20.	35.	65.	110.	170.	300.	
ELEVATION	340.	345.	347.	349.	352.	355.	360.	
CREL	SPWIS	COB	EWB	ELEV	COB	CAREA	ENPL	
345.3	345.3	345.3	345.3	345.3	345.3	345.3	345.3	
DAM DATA								
TOPEL	COB	EWB	ENPL	ENPL	ENPL	ENPL	ENPL	
318.9	318.9	318.9	318.9	318.9	318.9	318.9	318.9	
DAM BREACH DATA								
BRISIO	2	ELON	TFAIL	MSL	FAILL	MSL	FAILL	
270.	0.00	340.00	4.00	340.00	340.00	340.00	340.00	

STATION 2. PLAN 1, RATIO 6

END-OF-PERIOD HYDROGRAPH ORIGINATES

[illegible]

PEAK OUTFLOW IS 6416. AT TIME 16.75 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL
C/S	6616	3561	976	976	9369
C/S	108	191	26	26	262
INCHES	18.72	26.93	26.93	26.93	26.94
HP	479.46	928.46	928.46	928.46	928.44
AC-F1	1766	1935	1935	1935	1935
THOUS C/N	2176	2367	2367	2367	2367

THE BAN BREACH HYDROGRAPH WAS DEVELOPED USING A TIME INTERVAL OF .003 HOURS DURING BREACH FORMATION.
 DOWNSTREAM CALCULATIONS WILL USE A TIME INTERVAL OF .250 HOURS.
 THIS TABLE COMPARES THE HYDROGRAPH FOR DOWNSTREAM CALCULATIONS WITH THE COMPUTED BREACH HYDROGRAPH.
 INTERMEDIATE FLOWS ARE INTERPOLATED FROM END-OF-PERIOD VALUES.

TIME (HOURS)	TIME FROM BEGINNING OF BREACH (HOURS)	INTERPOLATED BREACH HYDROGRAPH (CFS)	COMPUTED BREACH HYDROGRAPH (CFS)	ERROR (CFS)	ACCUMULATED ERROR (CFS)	ACCUMULATED ERROR (AC-FT)
13.510	0.000	664.	664.	0.	0.	0.
13.513	0.003	1060.	1202.	-154.	-154.	-1.
13.517	0.007	1632.	1503.	-151.	-305.	-2.
13.520	0.010	1817.	1617.	-184.	-489.	-3.
13.523	0.013	1913.	1632.	-280.	-769.	-5.
13.527	0.017	1973.	1632.	-340.	-1109.	-8.
13.530	0.020	2000.	1632.	-368.	-1477.	-11.
13.533	0.023	2000.	1632.	-368.	-1845.	-14.
13.537	0.027	2000.	1632.	-368.	-2213.	-17.
13.540	0.030	2000.	1632.	-368.	-2581.	-20.
13.543	0.033	2000.	1632.	-368.	-2949.	-23.
13.547	0.037	2000.	1632.	-368.	-3317.	-26.
13.550	0.040	2000.	1632.	-368.	-3685.	-29.
13.553	0.043	2000.	1632.	-368.	-4053.	-32.
13.557	0.047	2000.	1632.	-368.	-4421.	-35.
13.560	0.050	2000.	1632.	-368.	-4789.	-38.
13.563	0.053	2000.	1632.	-368.	-5157.	-41.
13.567	0.057	2000.	1632.	-368.	-5525.	-44.
13.570	0.060	2000.	1632.	-368.	-5893.	-47.
13.573	0.063	2000.	1632.	-368.	-6261.	-50.
13.577	0.067	2000.	1632.	-368.	-6629.	-53.
13.580	0.070	2000.	1632.	-368.	-6997.	-56.
13.583	0.073	2000.	1632.	-368.	-7365.	-59.
13.587	0.077	2000.	1632.	-368.	-7733.	-62.
13.590	0.080	2000.	1632.	-368.	-8101.	-65.
13.593	0.083	2000.	1632.	-368.	-8469.	-68.
13.597	0.087	2000.	1632.	-368.	-8837.	-71.
14.000	0.090	2000.	1632.	-368.	-9205.	-74.
14.003	0.093	2000.	1632.	-368.	-9573.	-77.
14.007	0.097	2000.	1632.	-368.	-9941.	-80.
14.010	0.100	2000.	1632.	-368.	-10309.	-83.
14.013	0.103	2000.	1632.	-368.	-10677.	-86.
14.017	0.107	2000.	1632.	-368.	-11045.	-89.
14.020	0.110	2000.	1632.	-368.	-11413.	-92.
14.023	0.113	2000.	1632.	-368.	-11781.	-95.
14.027	0.117	2000.	1632.	-368.	-12149.	-98.
14.030	0.120	2000.	1632.	-368.	-12517.	-101.
14.033	0.123	2000.	1632.	-368.	-12885.	-104.
14.037	0.127	2000.	1632.	-368.	-13253.	-107.
14.040	0.130	2000.	1632.	-368.	-13621.	-110.
14.043	0.133	2000.	1632.	-368.	-13989.	-113.
14.047	0.137	2000.	1632.	-368.	-14357.	-116.
14.050	0.140	2000.	1632.	-368.	-14725.	-119.
14.053	0.143	2000.	1632.	-368.	-15093.	-122.
14.057	0.147	2000.	1632.	-368.	-15461.	-125.
14.060	0.150	2000.	1632.	-368.	-15829.	-128.
14.063	0.153	2000.	1632.	-368.	-16197.	-131.
14.067	0.157	2000.	1632.	-368.	-16565.	-134.
14.070	0.160	2000.	1632.	-368.	-16933.	-137.
14.073	0.163	2000.	1632.	-368.	-17301.	-140.
14.077	0.167	2000.	1632.	-368.	-17669.	-143.
14.080	0.170	2000.	1632.	-368.	-18037.	-146.
14.083	0.173	2000.	1632.	-368.	-18405.	-149.
14.087	0.177	2000.	1632.	-368.	-18773.	-152.
14.090	0.180	2000.	1632.	-368.	-19141.	-155.
14.093	0.183	2000.	1632.	-368.	-19509.	-158.
14.097	0.187	2000.	1632.	-368.	-19877.	-161.
14.100	0.190	2000.	1632.	-368.	-20245.	-164.
14.103	0.193	2000.	1632.	-368.	-20613.	-167.
14.107	0.197	2000.	1632.	-368.	-20981.	-170.
14.110	0.200	2000.	1632.	-368.	-21349.	-173.
14.113	0.203	2000.	1632.	-368.	-21717.	-176.
14.117	0.207	2000.	1632.	-368.	-22085.	-179.
14.120	0.210	2000.	1632.	-368.	-22453.	-182.
14.123	0.213	2000.	1632.	-368.	-22821.	-185.
14.127	0.217	2000.	1632.	-368.	-23189.	-188.
14.130	0.220	2000.	1632.	-368.	-23557.	-191.
14.133	0.223	2000.	1632.	-368.	-23925.	-194.
14.137	0.227	2000.	1632.	-368.	-24293.	-197.
14.140	0.230	2000.	1632.	-368.	-24661.	-200.
14.143	0.233	2000.	1632.	-368.	-25029.	-203.
14.147	0.237	2000.	1632.	-368.	-25397.	-206.
14.150	0.240	2000.	1632.	-368.	-25765.	-209.
14.153	0.243	2000.	1632.	-368.	-26133.	-212.
14.157	0.247	2000.	1632.	-368.	-26501.	-215.
14.160	0.250	2000.	1632.	-368.	-26869.	-218.
14.163	0.253	2000.	1632.	-368.	-27237.	-221.
14.167	0.257	2000.	1632.	-368.	-27605.	-224.
14.170	0.260	2000.	1632.	-368.	-27973.	-227.
14.173	0.263	2000.	1632.	-368.	-28341.	-230.
14.177	0.267	2000.	1632.	-368.	-28709.	-233.
14.180	0.270	2000.	1632.	-368.	-29077.	-236.
14.183	0.273	2000.	1632.	-368.	-29445.	-239.
14.187	0.277	2000.	1632.	-368.	-29813.	-242.
14.190	0.280	2000.	1632.	-368.	-30181.	-245.
14.193	0.283	2000.	1632.	-368.	-30549.	-248.
14.197	0.287	2000.	1632.	-368.	-30917.	-251.
14.200	0.290	2000.	1632.	-368.	-31285.	-254.
14.203	0.293	2000.	1632.	-368.	-31653.	-257.
14.207	0.297	2000.	1632.	-368.	-32021.	-260.
14.210	0.300	2000.	1632.	-368.	-32389.	-263.
14.213	0.303	2000.	1632.	-368.	-32757.	-266.
14.217	0.307	2000.	1632.	-368.	-33125.	-269.
14.220	0.310	2000.	1632.	-368.	-33493.	-272.
14.223	0.313	2000.	1632.	-368.	-33861.	-275.
14.227	0.317	2000.	1632.	-368.	-34229.	-278.
14.230	0.320	2000.	1632.	-368.	-34597.	-281.
14.233	0.323	2000.	1632.	-368.	-34965.	-284.
14.237	0.327	2000.	1632.	-368.	-35333.	-287.
14.240	0.330	2000.	1632.	-368.	-35701.	-290.
14.243	0.333	2000.	1632.	-368.	-36069.	-293.
14.247	0.337	2000.	1632.	-368.	-36437.	-296.
14.250	0.340	2000.	1632.	-368.	-36805.	-299.
14.253	0.343	2000.	1632.	-368.	-37173.	-302.
14.257	0.347	2000.	1632.	-368.	-37541.	-305.
14.260	0.350	2000.	1632.	-368.	-37909.	-308.
14.263	0.353	2000.	1632.	-368.	-38277.	-311.
14.267	0.357	2000.	1632.	-368.	-38645.	-314.
14.270	0.360	2000.	1632.	-368.	-39013.	-317.
14.273	0.363	2000.	1632.	-368.	-39381.	-320.
14.277	0.367	2000.	1632.	-368.	-39749.	-323.
14.280	0.370	2000.	1632.	-368.	-40117.	-326.
14.283	0.373	2000.	1632.	-368.	-40485.	-329.
14.287	0.377	2000.	1632.	-368.	-40853.	-332.
14.290	0.380	2000.	1632.	-368.	-41221.	-335.
14.293	0.383	2000.	1632.	-368.	-41589.	-338.
14.297	0.387	2000.	1632.	-368.	-41957.	-341.
14.300	0.390	2000.	1632.	-368.	-42325.	-344.
14.303	0.393	2000.	1632.	-368.	-42693.	-347.
14.307	0.397	2000.	1632.	-368.	-43061.	-350.
14.310	0.400	2000.	1632.	-368.	-43429.	-353.
14.313	0.403	2000.	1632.	-368.	-43797.	-356.
14.317	0.407	2000.	1632.	-368.	-44165.	-359.
14.320	0.410	2000.	1632.	-368.	-44533.	-362.
14.323	0.413	2000.	1632.	-368.	-44901.	-365.
14.327	0.417	2000.	1632.	-368.	-45269.	-368.
14.330	0.420	2000.	1632.	-368.	-45637.	-371.
14.333	0.423	2000.	1632.	-368.	-46005.	-374.
14.337	0.427	2000.	1632.	-368.	-46373.	-377.
14.340	0.430	2000.	1632.	-368.	-46741.	-380.
14.343	0.433	2000.	1632.	-368.	-47109.	-383.
14.347	0.437	2000.	1632.	-368.	-47477.	-386.
14.350	0.440	2000.	1632.	-368.	-47845.	-389.
14.353	0.443	2000.	1632.	-368.	-48213.	-392.
14.357	0.447	2000.	1632.	-368.	-48581.	-395.
14.360	0.450	2000.	1632.	-368.	-48949.	-398.
14.363	0.453	2000.	1632.	-368.	-49317.	-401.
14.367	0.457	2000.	1632.	-368.	-49685.	-404.
14.370	0.460	2000.	1632.	-368.	-50053.	-407.
14.373	0.463	2000.	1632.	-368.	-50421.	-410.
14.377	0.467	2000.	1632.	-368.	-50789.	-413.
14.380	0.470	2000.	1632.	-368.	-51157.	-416.
14.383	0.473	2000.	1632.	-368.	-51525.	-419.
14.387	0.477	2000.	1632.	-368.	-51893.	-422.
14.390	0.480	2000.	1632.	-368.	-52261.	-425.
14.393	0.483	2000.	1632.	-368.	-52629.	-428.
14.397	0.487	2000.	1632.	-368.	-52997.	-431.
14.400	0.490	2000.	1632.	-368.	-53365.	-434.
14.403	0.493	2000.	1632.	-368.	-53733.	-437.
14.407	0.497	2000.	1632.	-368.	-54101.	-440.
14.410	0.500	2000.	1632.	-368.	-54469.	-443.
14.413	0.503	2000.	1632.	-368.	-54837.	-446.
14.417	0.507	2000.	1632.	-368.	-55205.	-449.
14.420	0.510	2000.	1632.	-368.	-55573.	-452.
14.423	0.513	2000.	1632.	-368.	-55941.	-455.
14.427	0.517	2000.	1632.	-368.	-56309.	-458.
14.430	0.520	2000.	1632.	-368.	-56677.	-461.
14.433	0.523	2000.	1632.	-368.	-57045.	-464.
14.437	0.527	2000.	1632.	-368.	-57413.	-467.
14.440	0.530	2000.	1632.	-368.	-57781.	-470.
14.443	0.533	2000.	1632.	-368.	-58149.	-473.
14.447	0.537	2000.	1632.	-368.	-58517.	-476.
14.450	0.540	2000.	1632.	-368.	-58885.	-479.
14.453	0.543	2000.	1632.	-368.	-59253.	-482.
14.457	0.547	2000.	1632.	-368.	-59621.	-485.
14.460	0.550	2000.	1632.	-368.	-59989.	-488.
14.463	0.553	2000.	1632.	-368.	-60357.	-491.
14.467	0.557	2000.	1632.	-368.	-60725.	-494.
14.470	0.560	2000.	1632.	-368.	-61093.	-497.
14.473	0.563	2000.	1632.	-368.	-61461.	-500.
14.477	0.567	2000.	1632.	-368.	-61829.	-503.
14.480	0.570	2000.	1632.	-368.	-62197.	-506.
14.483	0.573	2000.	1632.	-368.	-62565.	-509.
14.487	0.577	2000.	1632.	-368.	-62933.</	

3. PLAN 1, RTIO 4

3. PLAN 1, RIG 4										
STATION	OUTFLOW									
	0	1	0	1	0	1	0	1	0	1
1	1	1	1	1	1	1	1	1	1	1
2	1	1	1	1	1	1	1	1	1	1
3	0	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0	0	0	0
5	0	0	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0	0	0
9	0	0	0	0	0	0	0	0	0	0
10	0	0	0	0	0	0	0	0	0	0
11	0	0	0	0	0	0	0	0	0	0
12	0	0	0	0	0	0	0	0	0	0
13	0	0	0	0	0	0	0	0	0	0
14	0	0	0	0	0	0	0	0	0	0
15	0	0	0	0	0	0	0	0	0	0
16	0	0	0	0	0	0	0	0	0	0
17	0	0	0	0	0	0	0	0	0	0
18	0	0	0	0	0	0	0	0	0	0
19	0	0	0	0	0	0	0	0	0	0
20	0	0	0	0	0	0	0	0	0	0
21	0	0	0	0	0	0	0	0	0	0
22	0	0	0	0	0	0	0	0	0	0
23	0	0	0	0	0	0	0	0	0	0
24	0	0	0	0	0	0	0	0	0	0
25	0	0	0	0	0	0	0	0	0	0
26	0	0	0	0	0	0	0	0	0	0
27	0	0	0	0	0	0	0	0	0	0
28	0	0	0	0	0	0	0	0	0	0
29	0	0	0	0	0	0	0	0	0	0
30	0	0	0	0	0	0	0	0	0	0
31	0	0	0	0	0	0	0	0	0	0
32	0	0	0	0	0	0	0	0	0	0
33	0	0	0	0	0	0	0	0	0	0
34	0	0	0	0	0	0	0	0	0	0
35	0	0	0	0	0	0	0	0	0	0
36	0	0	0	0	0	0	0	0	0	0
37	0	0	0	0	0	0	0	0	0	0
38	0	0	0	0	0	0	0	0	0	0
39	0	0	0	0	0	0	0	0	0	0
40	0	0	0	0	0	0	0	0	0	0
41	0	0	0	0	0	0	0	0	0	0
42	0	0	0	0	0	0	0	0	0	0
43	0	0	0	0	0	0	0	0	0	0
44	0	0	0	0	0	0	0	0	0	0
45	0	0	0	0	0	0	0	0	0	0
46	0	0	0	0	0	0	0	0	0	0
47	0	0	0	0	0	0	0	0	0	0

3. PLAN 1, RIG 4										
STATION	OUTFLOW									
	0	1	0	1	0	1	0	1	0	1
1	1	1	1	1	1	1	1	1	1	1
2	1	1	1	1	1	1	1	1	1	1
3	0	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0	0	0	0
5	0	0	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0	0	0
9	0	0	0	0	0	0	0	0	0	0
10	0	0	0	0	0	0	0	0	0	0
11	0	0	0	0	0	0	0	0	0	0
12	0	0	0	0	0	0	0	0	0	0
13	0	0	0	0	0	0	0	0	0	0
14	0	0	0	0	0	0	0	0	0	0
15	0	0	0	0	0	0	0	0	0	0
16	0	0	0	0	0	0	0	0	0	0
17	0	0	0	0	0	0	0	0	0	0
18	0	0	0	0	0	0	0	0	0	0
19	0	0	0	0	0	0	0	0	0	0
20	0	0	0	0	0	0	0	0	0	0
21	0	0	0	0	0	0	0	0	0	0
22	0	0	0	0	0	0	0	0	0	0
23	0	0	0	0	0	0	0	0	0	0
24	0	0	0	0	0	0	0	0	0	0
25	0	0	0	0	0	0	0	0	0	0
26	0	0	0	0	0	0	0	0	0	0
27	0	0	0	0	0	0	0	0	0	0
28	0	0	0	0	0	0	0	0	0	0
29	0	0	0	0	0	0	0	0	0	0
30	0	0	0	0	0	0	0	0	0	0
31	0	0	0	0	0	0	0	0	0	0
32	0	0	0	0	0	0	0	0	0	0
33	0	0	0	0	0	0	0	0	0	0
34	0	0	0	0	0	0	0	0	0	0
35	0	0	0	0	0	0	0	0	0	0
36	0	0	0	0	0	0	0	0	0	0
37	0	0	0	0	0	0	0	0	0	0
38	0	0	0	0	0	0	0	0	0	0
39	0	0	0	0	0	0	0	0	0	0
40	0	0	0	0	0	0	0	0	0	0
41	0	0	0	0	0	0	0	0	0	0
42	0	0	0	0	0	0	0	0	0	0
43	0	0	0	0	0	0	0	0	0	0
44	0	0	0	0	0	0	0	0	0	0
45	0	0	0	0	0	0	0	0	0	0
46	0	0	0	0	0	0	0	0	0	0
47	0	0	0	0	0	0	0	0	0	0

3. PLAN 1, RIG 4										
STATION	OUTFLOW									
	0	1	0	1	0	1	0	1	0	1
1	1	1	1	1	1	1	1	1	1	1
2	1	1	1	1	1	1	1	1	1	1
3	0	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0	0	0	0
5	0	0	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0	0	0
9	0	0	0	0	0	0	0	0	0	0
10	0	0	0	0	0	0	0	0	0	0
11	0	0	0	0	0	0	0	0	0	0
12	0	0	0	0	0	0	0	0	0	0
13	0	0	0	0	0	0	0	0	0	0
14	0	0	0	0	0	0	0	0	0	0
15	0	0	0	0	0	0	0	0	0	0
16	0	0	0	0	0	0	0	0	0	0
17	0	0	0	0	0	0	0	0	0	0
18	0	0	0	0	0	0	0	0	0	0
19	0	0	0	0	0	0	0	0	0	0
20	0	0	0	0	0	0	0	0	0	0
21	0	0	0	0	0	0	0	0	0	0
22	0	0	0	0	0	0	0	0	0	0
23	0	0	0	0	0	0	0	0	0	0
24	0	0	0	0	0	0	0	0	0	0
25	0	0	0	0	0	0	0	0	0	0
26	0	0	0	0	0	0	0	0	0	0
27	0	0	0	0	0	0	0	0	0	0
28	0	0	0	0	0	0	0	0	0	0
29	0	0	0	0	0	0	0	0	0	0
30	0	0	0	0	0	0	0	0	0	0
31	0	0	0	0	0	0	0	0	0	0
32	0	0	0	0	0	0	0	0	0	0
33	0	0	0	0	0	0	0	0	0	0
34	0	0	0	0	0	0	0	0	0	0
35	0	0	0	0	0	0	0	0	0	0
36	0	0	0	0	0	0	0	0	0	0
37	0	0	0	0	0	0	0	0	0	0
38	0	0	0	0	0	0	0	0	0	0
39	0	0	0	0	0	0	0	0	0	0
40	0	0	0	0	0	0	0	0	0	0
41	0	0	0	0	0	0	0	0	0	0
42	0	0	0	0	0	0	0	0	0	0
43	0	0	0	0	0	0	0	0	0	0
44	0	0	0	0	0	0	0	0	0	0
45	0	0	0	0	0	0	0	0	0	0
46	0	0	0	0	0	0	0	0	0	0
47	0	0	0	0	0	0	0	0	0	0

3. PLAN 1, RIG 4										
STATION	OUTFLOW									
	0	1	0	1	0	1	0	1	0	1
1	1	1	1	1	1	1	1	1	1	1
2	1	1	1	1	1	1	1	1	1	1
3	0	0	0	0	0	0	0	0	0	0
4	0	0	0	0	0	0	0	0	0	0
5	0	0	0	0	0	0	0	0	0	0
6	0	0	0	0	0	0	0	0	0	0
7	0	0	0	0	0	0	0	0	0	0
8	0	0	0	0	0	0	0	0	0	0
9	0	0	0	0	0	0	0	0	0	0
10	0	0	0	0	0	0	0	0	0	0
11	0	0	0	0	0	0	0	0	0	0
12	0	0	0	0	0	0	0	0	0	0
13	0	0	0	0	0	0	0	0	0	0
14	0	0	0	0	0	0	0	0	0	0
15	0	0	0	0	0	0	0	0	0	0
16	0	0	0	0	0	0	0	0	0	0
17	0	0	0	0	0	0	0	0	0	0
18	0	0	0	0	0	0	0	0	0	0
19	0	0	0	0	0	0	0	0	0	0
20	0	0	0	0	0	0	0	0	0	0
21	0	0	0	0	0	0	0	0	0	0
22	0	0	0	0	0	0	0	0	0	0
23	0	0	0	0	0	0	0	0	0	0
24	0	0	0	0	0	0	0	0	0	0
25	0	0	0	0	0	0	0	0	0	0
26	0	0	0	0	0	0	0	0	0	0
27	0	0	0	0	0	0	0	0	0	0
28	0	0	0							

MAXIMUM STORAGE • 2.

MAXIMUM STAGE IS	345.9
------------------	-------

HYDROGRAPH ROUTING

CHANNEL ROUTING - MODIFIED PULS - STATION 3 TO 4

ESTQA	ICCHP	ICCOR	ITAPE	JPL1	JPR7	IMARE	ISTAGE	ISAUTC
1	1	0	0	0	0	1	0	0
ROUTING DATA								
GLASS	CLASS	AVG	IMES	ISAME	LOPT	IPMP	LSTN	
0.0	0.000	0.00	1	1	0	0	0	
MSIPS	MSIOL	LAG	ANSKE	X	TSC	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	0.0	0	

NORMAL DEPTH CHANNEL ROUTING

CH11	CH21	CH31	CH41	CH51	CH61	CH71	CH81	CH91	CH101
0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

CROSS SECTION COORDINATES--STA, ELEV, STA, ELEV--ETC

STORAGE	OUTFLOW	STAGE	FLOW
0.00	0.00	0.00	0.00
100.00	100.00	100.00	100.00
200.00	200.00	200.00	200.00
300.00	300.00	300.00	300.00
400.00	400.00	400.00	400.00
500.00	500.00	500.00	500.00
600.00	600.00	600.00	600.00
700.00	700.00	700.00	700.00
800.00	800.00	800.00	800.00
900.00	900.00	900.00	900.00
1000.00	1000.00	1000.00	1000.00

STATION	PLAN 1, RTIO 4									
	OUTFLOW									
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.	1.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
35.	67.	60.	76.	91.	109.	126.	141.	161.	174.	186.
221.	294.	355.	409.	459.	502.	534.	563.	597.	623.	646.
370.	424.	469.	509.	546.	580.	610.	637.	662.	684.	704.
403.	437.	465.	489.	511.	531.	549.	565.	580.	594.	607.
426.	450.	469.	485.	498.	509.	518.	525.	530.	534.	537.
440.	455.	462.	467.	471.	474.	476.	478.	479.	480.	481.
454.	460.	464.	467.	469.	470.	471.	472.	473.	474.	475.
468.	471.	473.	474.	475.	476.	477.	478.	479.	480.	481.
482.	483.	484.	485.	486.	487.	488.	489.	490.	491.	492.
496.	497.	498.	499.	500.	501.	502.	503.	504.	505.	506.
510.	511.	512.	513.	514.	515.	516.	517.	518.	519.	520.
524.	525.	526.	527.	528.	529.	530.	531.	532.	533.	534.
538.	539.	540.	541.	542.	543.	544.	545.	546.	547.	548.
552.	553.	554.	555.	556.	557.	558.	559.	560.	561.	562.
565.	566.	567.	568.	569.	570.	571.	572.	573.	574.	575.
578.	579.	580.	581.	582.	583.	584.	585.	586.	587.	588.
591.	592.	593.	594.	595.	596.	597.	598.	599.	600.	601.
604.	605.	606.	607.	608.	609.	610.	611.	612.	613.	614.
617.	618.	619.	620.	621.	622.	623.	624.	625.	626.	627.
630.	631.	632.	633.	634.	635.	636.	637.	638.	639.	640.
643.	644.	645.	646.	647.	648.	649.	650.	651.	652.	653.
656.	657.	658.	659.	660.	661.	662.	663.	664.	665.	666.
669.	670.	671.	672.	673.	674.	675.	676.	677.	678.	679.
682.	683.	684.	685.	686.	687.	688.	689.	690.	691.	692.
695.	696.	697.	698.	699.	700.	701.	702.	703.	704.	705.
708.	709.	710.	711.	712.	713.	714.	715.	716.	717.	718.
721.	722.	723.	724.	725.	726.	727.	728.	729.	730.	731.
734.	735.	736.	737.	738.	739.	740.	741.	742.	743.	744.
747.	748.	749.	750.	751.	752.	753.	754.	755.	756.	757.
760.	761.	762.	763.	764.	765.	766.	767.	768.	769.	770.
773.	774.	775.	776.	777.	778.	779.	780.	781.	782.	783.
786.	787.	788.	789.	790.	791.	792.	793.	794.	795.	796.
799.	800.	801.	802.	803.	804.	805.	806.	807.	808.	809.
812.	813.	814.	815.	816.	817.	818.	819.	820.	821.	822.
825.	826.	827.	828.	829.	830.	831.	832.	833.	834.	835.
838.	839.	840.	841.	842.	843.	844.	845.	846.	847.	848.
851.	852.	853.	854.	855.	856.	857.	858.	859.	860.	861.
864.	865.	866.	867.	868.	869.	870.	871.	872.	873.	874.
877.	878.	879.	880.	881.	882.	883.	884.	885.	886.	887.
890.	891.	892.	893.	894.	895.	896.	897.	898.	899.	900.
903.	904.	905.	906.	907.	908.	909.	910.	911.	912.	913.
916.	917.	918.	919.	920.	921.	922.	923.	924.	925.	926.
929.	930.	931.	932.	933.	934.	935.	936.	937.	938.	939.
942.	943.	944.	945.	946.	947.	948.	949.	950.	951.	952.
955.	956.	957.	958.	959.	960.	961.	962.	963.	964.	965.
968.	969.	970.	971.	972.	973.	974.	975.	976.	977.	978.
981.	982.	983.	984.	985.	986.	987.	988.	989.	990.	991.
994.	995.	996.	997.	998.	999.	1000.	1001.	1002.	1003.	1004.
1007.	1008.	1009.	1010.	1011.	1012.	1013.	1014.	1015.	1016.	1017.
1020.	1021.	1022.	1023.	1024.	1025.	1026.	1027.	1028.	1029.	1030.
1033.	1034.	1035.	1036.	1037.	1038.	1039.	1040.	1041.	1042.	1043.
1046.	1047.	1048.	1049.	1050.	1051.	1052.	1053.	1054.	1055.	1056.
1059.	1060.	1061.	1062.	1063.	1064.	1065.	1066.	1067.	1068.	1069.
1072.	1073.	1074.	1075.	1076.	1077.	1078.	1079.	1080.	1081.	1082.
1085.	1086.	1087.	1088.	1089.	1090.	1091.	1092.	1093.	1094.	1095.
1098.	1099.	1100.	1101.	1102.	1103.	1104.	1105.	1106.	1107.	1108.
1111.	1112.	1113.	1114.	1115.	1116.	1117.	1118.	1119.	1120.	1121.
1124.	1125.	1126.	1127.	1128.	1129.	1130.	1131.	1132.	1133.	1134.
1137.	1138.	1139.	1140.	1141.	1142.	1143.	1144.	1145.	1146.	1147.
1150.	1151.	1152.	1153.	1154.	1155.	1156.	1157.	1158.	1159.	1160.
1163.	1164.	1165.	1166.	1167.	1168.	1169.	1170.	1171.	1172.	1173.
1176.	1177.	1178.	1179.	1180.	1181.	1182.	1183.	1184.	1185.	1186.
1189.	1190.	1191.	1192.	1193.	1194.	1195.	1196.	1197.	1198.	1199.
1202.	1203.	1204.	1205.	1206.	1207.	1208.	1209.	1210.	1211.	1212.
1215.	1216.	1217.	1218.	1219.	1220.	1221.	1222.	1223.	1224.	1225.
1228.	1229.	1230.	1231.	1232.	1233.	1234.	1235.	1236.	1237.	1238.
1241.	1242.	1243.	1244.	1245.	1246.	1247.	1248.	1249.	1250.	1251.
1254.	1255.	1256.	1257.	1258.	1259.	1260.	1261.	1262.	1263.	1264.
1267.	1268.	1269.	1270.	1271.	1272.	1273.	1274.	1275.	1276.	1277.
1280.	1281.	1282.	1283.	1284.	1285.	1286.	1287.	1288.	1289.	1290.
1293.	1294.	1295.	1296.	1297.	1298.	1299.	1300.	1301.	1302.	1303.
1306.	1307.	1308.	1309.	1310.	1311.	1312.	1313.	1314.	1315.	1316.
1319.	1320.	1321.	1322.	1323.	1324.	1325.	1326.	1327.	1328.	1329.
1332.	1333.	1334.	1335.	1336.	1337.	1338.	1339.	1340.	1341.	1342.
1345.	1346.	1347.	1348.	1349.	1350.	1351.	1352.	1353.	1354.	1355.
1358.	1359.	1360.	1361.	1362.	1363.	1364.	1365.	1366.	1367.	1368.
1371.	1372.	1373.	1374.	1375.	1376.	1377.	1378.	1379.	1380.	1381.
1384.	1385.	1386.	1387.	1388.	1389.	1390.	1391.	1392.	1393.	1394.
1397.	1398.	1399.	1400.	1401.	1402.	1403.	1404.	1405.	1406.	1407.
1410.	1411.	1412.	1413.	1414.	1415.	1416.	1417.	1418.	1419.	1420.
1423.	1424.	1425.	1426.	1427.	1428.	1429.	1430.	1431.	1432.	1433.
1436.	1437.	1438.	1439.	1440.	1441.	1442.	1443.	1444.	1445.	1446.
1449.	1450.	1451.	1452.	1453.	1454.	1455.	1456.	1457.	1458.	1459.
1462.	1463.	1464.	1465.	1466.	1467.	1468.	1469.	1470.	1471.	1472.
1475.	1476.	1477.	1478.	1479.	1480.	1481.	1482.	1483.	1484.	1485.
1488.	1489.	1490.	1491.	1492.	1493.	1494.	1495.	1496.	1497.	1498.
1501.	1502.	1503.	1504.	1505.	1506.	1507.	1508.	1509.	1510.	1511.
1514.	1515.	1516.	1517.	1518.	1519.	1520.	1521.	1522.	1523.	1524.
1527.	1528.	1529.	1530.	1531.	1532.	1533.	1534.	1535.	1536.	1537.
1540.	1541.	1542.	1543.	1544.	1545.	1546.	1547.	1548.	1549.	1550.
1553.	1554.	1555.	1556.	1557.	1558.	1559.	1560.	1561.	1562.	1563.
1566.	1567.	1568.	1569.	1570.	1571.	1572.	1573.	1574.	1575.	1576.
1579.	1580.	1581.	1582.	1583.	1584.	1585.	1586.	1587.	1588.	1589.
1592.	1593.	1594.	1595.	1596.	1597.	1598.	1599.	1600.	1601.	1602.
1605.	1606.	1607.	1608.	1609.	1610.	1611.	1612.	1613.	1614.	1615.
1618.	1619.	1620.	1621.	1622.	1623.	1624.	1625.	1626.	1627.	1628.
1631.	1632.	1633.	1634.	1635.	1636.	1637.	1638.	1639.	1640.	1641.
1644.	1645.	1646.	1647.	1648.	1649.	1650.	1651.	1652.	1653.	1654.
1657.	1658.	1659.	1660.	1661.	1662.	1663.	1664.	1665.	1666.	1667.
1670.	1671.	1672.	1673.	1674.	1675.	1676.	1677.	1678.	1679.	1680.
1683.	1684.	1685.	1686.	1687.	1688.	1689.	1690.	1691.	1692.	1693.
1696.	1697.	1698.	1699.	1700.	1701.	1702.	1703.	1704.	1705.	1706.
1709.	1710.	1711.	1712.	1713.	1714.	1715.	1716.	1717.	1718.	1719.
1722.	1723.	1724.	1725.	1726.	1727.	1728.	1729.	1730.	1731.	1732.
1735.	1736.	1737.	1738.	1739.	1740.	1741.	1742.	1743.	1744.	1745.
1748.	1749.	1750.	1751.	1752.	1753.	1754.	1755.	1756.	1757.	1758.
1761.	1762.	1763.	1764.	1765.	1766.	1767.	1768.	1769.	1770.	1771.
1774.	1775.	1776.	1777.	1778.	1779.	1780.	1781.	1782.	1783.	1784.
1787.	1788.	1789.	1790.	1791.	1792.	1793.	1794.	1795.	1796.	1797.
1799.	1800.	1801.	1802.	1803.	1804.	1805.	1806.	1807.	1808.	1809.
1812.	1813.	1814.	1815.	1816.	1817.	1818.	1819.	1820.	1821.	1822.
1825.	1826.	1827.	1828.	1829.	1830.	1831.	1832.	1833.	1834.	1835.
1838.	1839.	1840.	1841.	1842.	1843.	1844.	1845.	1846.	1847.	1848.
1851.	1852.	1853.	1854.	1855.	1856.	1857.	1858.	1859.	1860.	1861.
1864.	1865.	1866.	1867.	1868.	1869.	1870.	1871.	1872.	1873.	1874.
1877.	1878.	1879.	1880.	1881.	1882.	1883.	1884.	1885.	1886.	1887.
1890.	1891.	1892.	1893.	1894.	1895.	1896.	1897.	1898.	1899.	1900.
1903.	1904.	1905.	1906.	1907.	1908.	1909.	1910.	1911.	1912.	1913.
1916.	1917.	1918.	1919.	1920.	1921.	1922.	1923.	1924.	1925.	1926.
1929.	1930.	1931.	1932.	1933.	1934.	1935.	1936.	1937.	1938.	1939.
1942.	1943.	1944.	1945.	1946.	1947.	1948.	1949.			

[illegible][illegible]

CROSS SECTION COORDINATES--STA, ELEV, STA, ELEV--ETC

STORAGE	0.88	2.83	5.06	5.46	35.26	33.59	59.55	90.58	119.46	133.54
	189.71	289.24	269.16	312.47	359.17	466.27	456.76	606.50	566.52	622.59
OUTFLOW	0.88	97.61	316.11	596.37	1196.69	2512.66	5812.98	9662.91	13357.03	15916.67
	25676.03	33351.33	42070.11	51050.13	62744.16	74798.24	87498.66	102291.51	117677.16	137113.29
STAGE	266.08	266.74	267.47	268.21	268.95	269.68	268.62	269.16	269.89	262.63
	265.37	266.11	267.04	268.58	268.32	269.75	267.79	268.51	269.26	263.86
FLOW	0.88	97.61	186.11	596.37	1196.69	2512.66	5812.98	9662.91	13357.03	15916.67
	25676.03	33351.33	42070.11	51050.13	62744.16	74798.24	87498.66	102291.51	117677.16	137113.29

STATION 5, PLAN 1, RTG 4

[illegible]

MAXIMUM STORAGE - 69.

MAXIMUM STAGE IS 290.7

BREACH

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	1	RATIO	2	RATIO	3	RATIO	4	RATIOS APPLIED TO FLOWS
						.10	.15	.50	1.00			
HYDROGRAPH AT	1	1.77	1	514.	922.	3072.	5142.					
		4.501	1	17.501	26.851	88.501	173.961					
ROUTED TO	2	1.77	1	419.	1465.	3554.	6414.					
		4.501	1	11.071	41.501	108.641	181.621					
ROUTED TO	3	1.77	1	428.	1469.	3567.	6404.					
		4.501	1	11.091	41.601	108.991	181.331					
ROUTED TO	4	1.77	1	414.	1369.	3392.	6274.					
		4.501	1	11.031	38.771	96.851	177.771					
ROUTED TO	5	1.77	1	418.	1371.	3369.	6269.					
		4.501	1	11.031	37.781	95.401	177.431					

BREACH

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1					ELEVATION STORAGE CUTFLOW		INITIAL VALUE 349.30 65. 8.		SPILLWAY CREST 349.30 65. 8.		TOP OF DAM 352.00 120. 450.				
RATIO OF PMF		MAXIMUM RESERVOIR H.S. ELEV		MAXIMUM DEPTH OVER DAM		MAXIMUM STORAGE AC-FT		MAXIMUM OUTFLOW CFS		DURATION OVER TOP HOURS		TIME OF MAX OUTFLOW HOURS		TIME OF FAILURE HOURS	
.10		352.93		0.00		121.		419.		0.00		17.75		0.00	
.15		353.13		.23		133.		1402.		.50		17.33		16.75	
.20		353.12		.22		132.		3556.		.50		16.83		16.25	
1.00		353.29		.39		136.		6414.		.75		16.75		13.50	

PLAN 1				STATION 3			
RATIO		MAXIMUM FLOW-CFS		MAXIMUM STAGE-FT		TIME HOURS	
.10		420.		348.9		17.75	
.15		1469.		342.8		17.50	
.20		3557.		344.5		16.75	
1.00		6404.		345.9		16.75	

PLAN 1				STATION 4			
RATIO		MAXIMUM FLOW-CFS		MAXIMUM STAGE-FT		TIME HOURS	
.10		510.		312.0		10.00	
.15		1300.		313.8		17.50	
.20		2270.		316.0		17.00	
1.00		6270.		317.5		17.00	

PLAN 1				STATION 5			
RATIO		MAXIMUM FLOW-CFS		MAXIMUM STAGE-FT		TIME HOURS	
.10		510.		207.0		10.00	
.15		1331.		209.0		17.75	
.20		2360.		209.9		17.00	
1.00		6260.		209.7		17.00	

WALL
C

BOROUGH

CANTERBURY

OF

BOWING

KEY MAP

SCALE 1" = 100'

22.70

EL. 352.90

EL. 351.19

EL. 349.27

6" CIP

REMOVE CONC. BLOCKS
FROM MOUTH OF
SPILLWAY

CRYSTAL SPRING
LAKE
WATER EL. 347.83 (MAY 7, 1964)

EXIST. SPILLWAY APRON EL. 342.25


MASONRY WALL

DE WALL

SECTION "B-B"

SAND BLAST EXPOSED STEEL ST.
FASTEN WIRE MESH REINFORCING
STRINGERS WITH EXPANSION ANCHORS
AND RESTORE WITH "GUNIT" MORTAR

D-39




SECTION "A-A"

DAMS IN NEW JERSEY—REFERENCE DATA

No. 23-77

Name of Owner Ramsey Country Club Estates Address Ramsey, N. J.
 Name of Dam _____ County Bergen Location 23.32.6.5.9 ☐
 CONSTRUCTION: Date Before 1923 By whom _____
 Stream Ramsey Brook Tributary to Honokus Creek
 DRAINAGE BASIN: Area 1.77 sq. mi. Description Hilly, undeveloped
 Description of valley below dam Base of Allendale 1 mi. downstream
 DAMAGE FROM FAILURE: Probable Heavy
 Previous (date) _____
 Purpose Soil Erosion Development Type _____
 Foundation Unknown
 Length 525 ft. Max. height 12 ft. ^{13 ft.} width of top 24 ft.
 Upstream slope Unknown Downstream slope 1:1 Volume _____ Cu. yds.
 SPILLWAY: Type 2.25' wide concrete wall (C-249) Length 30 ft.
 Depth below top of dam 3.33 ft. Capacity 161 at 2.2' hls. c. f. s. per sq. mi.
 RESERVOIR: Capacity _____ mill. gals. Area 30 acres. Length _____ ft.
 Outlets _____
 Remarks Flat slab concrete bridge over spillway, 2.2' high clear opening, crest to bridge underclearance, 12' wide bituminous road along top of dam.
 Sources of data _____ Inspection H.C.W. Date 7/10/45



1000 0 1000 2000 3000 4000 5000 6000
 SCALE IN FEET



AREA LOCATION

CRYSTAL SPRING DAM

JENNY - LEEDSHILL

JANUARY 1979





Plate D-3



TECHNICAL / LEADS/ALL JAN. 1979

Plate D-4

